M/s MEZZAN QATAR	QREF 04/12/24-1		
Kind Attn: Mr Hossam Eldaly Maintenance Manager D: +974 4 452 4155 M: +974 6651 3409	Subject: Design, Supply, Installation, Testing & Commissioning of Package AC Units for Water Factory Warehouse		
E: hossam.eldaly@mezzan.com	Location: INDUSTRIAL AREA		
DATE: 04/12/2024	Email: mes@mes.qa		

Dear Sir.

With reference to your inquiry concerning Design, Supply, Installation, Testing & Commissioning of Package AC Units, we would like to submit our proposal, which took into consideration all your requirements for this project's scope of work. **Attached the covered Areas.**

Scope of works:

- Design, Supply, Installation, testing and commissioning of 3 nos. PACKAGED air conditioning units + 1 nos. Duct Split without duct For Bottling Room. (Brand: COOLEX KUWAIT) to maintain +25 C deg temperature
- 2. Supply & Installation **Textile Duct lines to cover the target areas** for proper air distribution inside the warehouse. Outside duct will **be GI Duct** with Thermobreak Insulation.
- 3. Supply & Installation of Steel Frame + PVC Curtains to close the gaps around the cooled area.
- 4. Supply & Installation of 6 nos Wall Mounted Split ACs for 3 small rooms
- 5. All holes to be properly fixed and sealed.
- 6. Provide necessary Lifting Equipment & Scaffolds for installation.
- 7. Provide concrete plinth for all AC units.
- 8. Testing & Commissioning of the above.

Excluding: Any Electrical works to feed the units. Dismantling of racking system or shifting any stored materials will be client responsibility to enable proper installation of AC systems and related components.

Warranty: 1 year full + 4 additional years for compressors

Tel: 44459207 - Fax: 44780499 - P.O.Box: 23107 E-mail: mes@mes.qa - Web: www.mes.qa



BOQ – WATER FACTORY

DESCRIPTION		UNIT PRICE	TOTA L	
1) Supply & Installation of PACKAGE ACs made by COOLEX KUWAIT	3	245,000	735,000	
3 NOS SPU540 PACKAGE Acs (SEE ATTACHED DRAWING)				
(2 x serving the factory area)				
(1 x serving the Production Area)				
2) Supply & Installation of Split AC system Consisting of indoor FCU + out door condensing unit without duct (serving Bottling Room)		50,000	50,000	
3) Supply & Installation of PVC Partitions with Steel Frame to close the gaps		115,000	115,000	
around the cooled area to avoid infiltration.				
4) Supply & Installation of 6 nos Split ACs for water treatment room,		3,900	23,400	
machine room.				
5) Supply & Installation of Textile Duct (Internal duct)		INCLUDED	INCLUDED	
6) Supply & Installation of GI duct (external duct) with Thermobreak Insulation		INCLUDED	INCLUDED	
7) Plinth for AC units		INCLUDED	INCLUDED	
8) Testing & Commissioning	LS	INCLUDED	INCLUDED	
<u>LUMP SUM PRICE FOR ABOVE WORKS =</u>		923,400 Q.R.		

Delivery Time: 12 → 14 weeks from advanced payment date & PTW

Offer Validity: This proposal is valid for 7 days

Payment Terms:

- 1-40% advance payment against our company cheque to be returned back to us upon delivering the ACs at site.
- 2-25% upon delivering the ACs to site
- 3-25% against invoices related to the progress of works.
- 4-5% against testing and commissioning
- 5-5% retention to be paid after one year.

Assuring you our professional cooperation

METRI ENGINEERING SERVICES W.L.L



Tel: 44459207 - Fax: 44780499 - P.O.Box: 23107 E-mail: mes@mes.qa - Web: www.mes.qa

