

M/s American Internat	tional QREF 09/09/2024-5-rev2
Contractors Inc. Kind Attn: Mr Ramadas Amba	Subject: Quotation for HVAC TAB works (Air Balancing) + HVAC Equipment Commissioning
E-Mail: rambakkat@aici-ho.com	<u>Project Title: HVAC Troop Warehouse – Al</u>
Mobile : +97466715288	<u>Udeid</u>
DATE: 09/09/2023	Email: mes@mes.qa

Dear Sir,

With reference to your email, please find below scope of works which covers Air HVAC related equipment & Air Terminals as per the attached schedule :

Scope of Works:

- 1. **Air Balancing:** This section covers the performance check & balancing for all Air Systems as detailed in the schedule of equipment attached. All measuring, balancing techniques and instrumentation utilized are in accordance with the current NEBB standards and all instrumentations are with valid calibration certificates. All ducted systems will be measured and balanced manometers, anemometer, air flow hood for balancing air terminals. All major fans will be checked for correct rotation, motor running currents, running speeds, system pressures and total air volume. All readings will be recorded and presented in tabulated format as per NEBB standard.
 - 2. Commissioning of Above Systems as per the manufacturer.

Lump Sum Price for the HVAC Air Balancing + Commissioning = 44,500 Q.R.

Tel: 44459207 - Fax: 44780499 - P.O.Box: 23107 E-mail: mes@mes.ga - Web: www.mes.ga



Excluding:

- Ceiling openings & access where required for hidden test points to be provided by client
- Any kind of duct modification or accessories to the existing duct. Any required repair to the existing units or ducts is excluded and the above price doesn't include re-current visits and re-measurement.
- Any Leak rectification for ducts.
- Equipment Startup and Initial commissioning reports by Equipment Supplier/Contractor.
- DRVs or PICVs where not available & Test Plugs.
- Ceiling openings where required for hidden DRVs to be provided by client
- Startup, Testing & Commissioning of Chillers, Pumps, AHUs, FCUs by Supplier.
- Any kind of water flushing and chemical treatment.
- Any Leak rectification from chilled water pipes.
- Strainers cleaning.
- Lifting equipment where needed to perform the measurement and adjustment.
- All systems and ducts should be ready before we start the commissioning process. A Pre-commissioning
 tests should be carried out by the client's contractor and submitted to us with all relevant datasheets.
- Anything not mentioned in the above scope.

Payment Terms: 50% Advance along with order

50% Against final report submission

METRI ENGINEERING SERVICES

Fayez METRI (55572793 / 70500311)

للغدمات الهندسية

P.O. Box 19962, Doha-Qatar TelFax: 4412767

Tel: 44459207 - Fax: 44780499 - P.O.Box: 23107 E-mail: mes@mes.ga - Web: www.mes.ga