To: M/s Sky steel iron & aluminum Doha

Attn: MR. MD afjal Mobile: +97450737213

E-mail: afjalmd6871@gmail.com


Sub : Supply & Installation of Walk In Cold Room Ref. #: 9820-1-rev1

Dear Sir,

With reference to your inquiry, we are pleased to submit our proposal for your above requirements to wit:

SCOPE OF WORK : Supply, installation, Testing & Commissioning of 1 no Walk in

Cold Rooms (1 Chiller)



Cold Room #1: Consisting of 1 Chiller Room

EXTERNAL Dimensions: AS PER ABOVE DIMENSIONS X HEIGHT 2.4M

(PUR Wall & PUR Ceiling PANEL THICKNESS 80mm)

Doors : 1no Single Leaf Hinged Door 0.9m x 1.9m with heater for each room

Floor Insulation : none

Refrigeration Units: 1no Condensing Unit + 1no Matching Evaporator

Copeland or Tecumseh

Sandwich Panel INSULATION : PUR (POLYURTHANE) (Made in Qatar)

THICKNESS: 80 mm

CLADDING : 0.4 mm pre-painted GI sheets.

Tel: 44459207 - Fax: 44780499 - P.O.Box: 23107 E-mail: mes@mes.qa - Web: www.mes.qa **CONSTRUCTION** : Panels are joined together by means of tongue and

groove and locked together on each side of the

panel to ensure air tight joints.

DOOR ACCESSORIES: Door is complete with fittings and accessories and

have the same finish and thickness as that of the walls and ceiling, complete with rubber gaskets.

Lighting : LED lights Included to provide the appropriate

light levels for each cold store.

Ref. Accessories : All accessories such as expansion valve, solenoid,

sight glass, pressure relief valves ...etc are $\,$

included

CONTROL PANEL : Specially designed to control & secure the system.

1 no. control panel for each cold room will be provided with necessary contactor,

overload relay, signal lights...etc

PIPES : copper pipes are made by Muller Brass or

Equivalent

M/ ACCESSORIES : Will be provided including rivets, internal and

external flashing, silicon and hygienic plastic

corners.

Excluding : Electrical Power to be arranged by client at site &

Any Civil Works.

NET PRICE FOR ABOVE = 45,000 Q.R.

PAYMENT TERMS : 60% advance

20% upon delivery of cooling units

20% upon Completion

DELIVERY : 2 TO 3 WEEKS from the date of your firm order

along with the receipt of down payment provided

the site is ready for installation.

WARRANTY : 1 year on all materials supplied and installed by

MES + free preventive maintenance for the 1^{st} year. Servicing other than MES authorized technician voids warranty. Sandwich Panels 5 years

warranty.

NOTE: All civil works and main power EXCLUDED. Our work is limited to the above quoted. Delay of delivery due to acts of 3rd party (non-availability of supply); site readiness; accidents will not be accounted to MES. Warranty does not cover force majeure, loss due to fire or damage due to natural calamities. MES will not be held liable for any damage on products or items inside the cold room.

VALIDITY : 30 days.

We trust the above quotation merits your attention and we look forward to serving your requirement soon. Should you need any further clarification, please do not hesitate to contact us.

Thanks & regards,

Metri Engineering Services W.L.L







Tel: 44459207 - Fax: 44780499 - P.O.Box: 23107 E-mail: mes@mes.qa - Web: www.mes.qa







Tel: 44459207 - Fax: 44780499 - P.O.Box: 23107 E-mail: mes@mes.qa - Web: www.mes.qa