COMMERCIAL PROPOSAL

HVAC System Annual Maintenance Contract (AMC)

Preventive Planned Maintenance & Servicing

Project:	Villa 20, West Bay Lagoon, Doha, Qatar
Client:	**Construction Development Company LLC**
Ref:	RFQ – HVAC System Servicing (Villa 20 WBL)
Date:	14 April 2026

1. Introduction

Metri Engineering Services W.L.L. (MES) is pleased to submit this commercial proposal in response to your Request for Quotation dated 13 April 2026 for the HVAC system servicing at Villa 20, West Bay Lagoon, Doha, Qatar.

2. Equipment Covered

The following HVAC equipment installed at Villa 20 is covered under this AMC, as per the provided as-built drawings (P-266-IDC-HVAC-100 & P-266-IDC-HVAC-101) and BOQ:

SN	Description	Model	Qty	Location
1	Concealed Ducted Heat Pump FCU	LXTdMO-055R0M3HP	2	GF & FF
2	Concealed Ducted Heat Pump FCU	LXTdMO-048R0M3HP	1	FF
3	Concealed Ducted Heat Pump FCU	LXTdMO-036R0T3HP	4	GF & FF
4	Fresh Air Handling Unit (FAHU) – DX Type with Samsung DVMS VRF Outdoor Condensing Unit, EU-4, EU-9 Bag & H13 HEPA Filters, UV Light, EC Fan	-	1	Roof
5	Ducted Split Unit (1.5 Ton)	-	1	GF Tech. Room
6	Concealed Inline Exhaust Fans	-	3	GF, FF & Roof

3. Scope of Work

This AMC covers the following services, strictly as requested:

- Full preventive planned maintenance (PPM) servicing of all 7 concealed ducted heat pump FCUs with dedicated outdoor units
- Full PPM servicing of the FAHU (DX type) and Samsung DVMS VRF outdoor condensing unit on the roof
- Full PPM servicing of the ducted split unit (1.5 Ton) at the ground floor technical room
- Maintenance of all 3 concealed inline exhaust fans (GF, FF, and Roof)
- Supply and return grille/diffuser cleaning.

3.1 PPM Frequency

Total visits per year: 4

Visits will be scheduled quarterly in coordination with the client/site representative.

4. Detailed Scope of Work Per Visit

The following checklists detail the specific maintenance tasks performed during each Minor and Major PPM visit:

4.1 Concealed Ducted Heat Pump Fan Coil Units (7 Nos.) and Outdoor Units

SN	Description	Minor	Major
1	Check unit for abnormal noise and vibration	✓	✓
2	Inspect casing, access panels, and insulation condition	✓	✓
3	Check for any visible damage or corrosion	✓	✓
4	Verify thermostat operation and setpoint accuracy	✓	✓
5	Clean air filters	✓	✓
6	Inspect coil surface for dust/dirt	✓	✓
7	Clean coils (basic – air blowing)	✓	✓
8	Check fan rotation and noise	✓	✓
9	Inspect motor condition (visual check)	✓	✓
10	Clean drain tray	✓	✓
11	Check condensate drain line for blockage	✓	✓
12	Verify no water leakage	✓	✓
13	Inspect air grilles and diffusers	✓	✓
14	Inspect control wiring and connections	✓	✓
15	Check power supply and voltage	✓	✓
16	Tighten all mechanical fasteners		✓
17	Tighten all electrical terminals		✓
18	Check for leaks in coil		✓
19	Drain system deep cleaning		✓
20	Check vibration isolators		✓
21	Straighten coil fins (if bent)		✓
22	Clean blower wheel		✓
23	Check motor amperage		✓
24	Check contactors, relays, and capacitors		✓
25	Check sensors and actuators		✓

4.2 Fresh Air Handling Unit (FAHU) and Samsung DVMS VRF Outdoor Condensing Unit

SN	Description	Minor	Major
1	Visual inspection of unit condition	✓	✓
2	Check abnormal noise and vibration	✓	✓
3	Inspect casing, panels, and insulation	✓	✓
4	Clean air filters	✓	✓
5	Inspect air filters condition	✓	
6	Visual inspection of coils	✓	✓
7	Basic cleaning of coils (air blowing)	✓	✓
8	Check fan rotation and noise	✓	✓
9	Inspect motor condition	✓	✓
10	Clean drain tray	✓	✓
11	Inspect drain tray and piping	✓	✓
12	Check for blockage/leakage	✓	✓
13	Inspect fresh air intake and louvers	✓	✓
14	Check damper operation	✓	✓
15	Inspect wiring and connections	✓	✓
16	Check fan motor and blades	✓	✓
17	Check for visible refrigerant leaks	✓	✓
18	Clean indoor unit filters	✓	✓
19	Inspect blower and coil	✓	✓
20	Visual inspection and cleaning (VRF outdoor unit)	✓	✓
21	Tightening of mechanical fittings		✓
22	Check vibration isolators		✓
23	Check coil leakage/corrosion		✓
24	Straighten coil fins (if bent)		✓
25	Clean blower/impeller		✓
26	Check motor current		✓
27	Flush drain line		✓
28	Clean condenser coil		✓
29	Inspect compressor operation		✓
30	Deep cleaning of unit		✓
31	Tighten electrical terminals		✓
32	Check contactors/relays		✓

4.3 Ducted Split AC (1.5 Ton)

SN	Description	Minor	Major
1	Visual inspection of indoor and outdoor units	✓	✓
2	Check for abnormal noise or vibration	✓	✓
3	Inspect panels, casing, and insulation	✓	✓
4	Clean air filters	✓	✓
5	Inspect indoor and outdoor coils	✓	✓
6	Clean coils (basic)	✓	✓
7	Check fan rotation and noise	✓	✓
8	Inspect motor and blower	✓	✓
9	Check condensate drain tray and pipe	✓	✓
10	Check power supply	✓	✓
11	Inspect wiring and terminals	✓	✓
12	Deep clean coils		✓
13	Flush drain line		✓
14	Tighten electrical connections		✓

4.4 Concealed Inline Exhaust Fans (3 Nos.)

SN	Description	Minor	Major
1	Inspect fan housing and impeller	✓	✓
2	Clean impeller and casing	✓	✓
3	Check unusual vibration and noise	✓	✓
4	Inspect belt and pulley condition (if applicable)	✓	✓
5	Check airflow direction and performance	✓	✓
6	Inspect electrical connections	✓	✓
7	Check motor bearings and lubrication		✓

4.5 Supply and Return Grilles/Diffusers Cleaning

SN	Description	Minor	Major
1	Remove supply and return grilles/diffusers	✓	✓
2	Dust and debris removal	✓	✓

5. Commercial Offer

5.1 AMC Base Price

SN	Description	No. of Visits	Total Price (QAR)
1	PPM visits for all above-mentioned equipment	4	**12,000**
	TOTAL AMC NET AMOUNT (FOR 1 YEAR – 4 VISITS)	**4**	

5.2 Additional Rates

SN	Description	Rate (QAR)
1	Filter replacement – per FCU	300
2	Filter replacement – per AHU/FAHU	1,500
3	Emergency call-out charge (per visit, parts/repairs excluded)	200
4	Spare parts and repairs	To be quoted separately when needed

5.3 Optional Item (Quoted Separately)

SN	Description	Price (QAR)
1	Complete ductwork network cleaning (one-time)	**8,500**

6. Inclusions

- All labor costs for 4 scheduled PPM visits per year
- Transportation to and from site for all scheduled visits
- All necessary PPM tools, instruments, and cleaning materials/chemicals
- Supply and return grille/diffuser cleaning
- Inspection and cleaning of all indoor and outdoor units as per checklists
- PPM service reports after each visit

7. Exclusions

- Spare parts, replacement components, and refrigerant top-up (to be quoted separately on a case-by-case basis when required)
- Filter replacements (charged separately as per rates in Section 5.2)
- Repair works, including electrical and mechanical repairs (to be quoted and invoiced separately when required)
- Ductwork cleaning (quoted as optional item in Section 5.3)
- Any civil, structural, or plumbing works
- Modifications or alterations to the existing HVAC system or ceiling
- Any works not explicitly stated in Section 3 and Section 4 of this proposal

8. HVAC Servicing Methodology

MES employs the following tools, equipment, and methodology for HVAC servicing:

- Coil cleaning: Compressed air blowing for basic cleaning; chemical wash with coil cleaner and pressure washer for deep cleaning
- Filter servicing: Compressed air cleaning; replacement with equivalent filters when required
- Grille/diffuser cleaning: Removal, soaking in anti-bacterial solution, pressure wash, mould treatment, and reinstallation
- Electrical checks: Digital multimeter, clamp meter for amperage/voltage readings, IR thermometer
- General: Standard HVAC hand tools, torque wrenches, fin combs.

8.1 Duct Cleaning Methodology (Optional Item)

If the optional ductwork cleaning is approved, MES will employ the following:

- Mechanical agitation using rotary brush systems
- Negative air pressure extraction with HEPA-filtered vacuum equipment
- before and after cleaning for documentation
- Full photographic report with before/after images

9. Project References

MES has successfully executed similar residential HVAC maintenance contracts across Qatar, including but not limited to:

- Al Wajba Palace – HVAC maintenance and servicing
- Dr. Al Horr Villa – HVAC annual maintenance contract
- Various other high-profile residential and commercial clients across Qatar

Detailed reference letters are available upon request.

10. General Terms and Conditions

- This quotation is valid for 30 days from the date of submission.
- Payment terms: 50% Advance, 50% After Six months.
- AMC period: 12 months from the date of contract signing / first PPM visit.
- PPM scheduling: Quarterly, in coordination with the client's site representative.
- Emergency call-out response: Within 4 hours of request, subject to availability.
- All prices are in Qatari Riyals (QAR) and exclusive of VAT (if applicable).
- Company profile and valid Qatar CR copy will be attached with the submission email.

We trust that this proposal meets your requirements and look forward to the opportunity to be of service. Should you require a site visit, further clarification, or any additional information, please do not hesitate to contact us.

METRI ENGINEERING SERVICES W.L.L.
Eng. Fayez Metri 55572793

متري للخدمات الهندسية ذ.م.م
ص.ب: ١٩٩٦٢، الدوحة - قطر
تليفكس: ٤٤١٢٧٦٧
P.O. Box 19962, Doha-Qatar
TelFax: 4412767
METRI ENGINEERING SERVICES W.L.L