

M/s Gulf Warehousing Company	QREF 02/06/26-10 Subject: <u>COMMERCIAL</u>: Supply & installation of Package Acs for warehouse area + Battery Room Exhaust Fan + Duct Works. Location : QAF Shamal WH#5
DATE: 02/06/2026	Email: mes@mes.qa

Dear Sir,

With reference to your inquiry concerning Supply & installation of Supply & installation of Package Acs for warehouse area + Battery Room Exhaust Fan + Duct Works @ QAF Shamal WH#5, we would like to submit our proposal, which took into consideration all your requirements for this project's scope of work.

Scope of works:

1. Supply, Installation, testing and commissioning of **2 nos.** additional **PACKAGED** air conditioning (Brand: **CLIMACs**) for warehouse area to maintain **+22C Deg & RH% less than 80% All times.**
2. Supply & Installation of 2 nos. Duct Heaters in the package Acs or main duct to control humidity levels in the warehouse.
3. Supply & Installation of Smoke/Fire Motorized Dampers 4 nos.
4. Supply & Installation Internal GI Duct works with insulation along the wall with Supply/Return Grilles.
5. Supply & Installation of External GI Duct Works with insulation & Aluminum cladding
6. Supply & installation of Exhaust Fans (1 Duty + 1 Standby) with Duct works for battery room area.
7. Supply & Installation of portable dehumidifier for battery room to maintain the RH% levels
8. Supply & Installation of Additional Wall Split Acs 2 nos for Battery Rooms.
9. Supply & Installation of Wifi Thermostat that can control the package AC operation and temperature settings from onsite and remotely through dedicated APP. Wifi signal to be provided by client at site.

10. Supply & Installation of Wi-Fi Temp/RH% monitoring units 4 nos. to measure and log continuously warehouse temp/RH% with alarming via app or emails. The monitoring units can be accessed onsite or through web/App to view current readings, history readings and create reports. Wifi signal to be provided by client at site.
11. Provide concrete plinth to suit the new package ACs.
12. Wall opening and closing properly.
13. Provide Condensate Drainpipes and connect to nearest drain point at site.
14. Electrical Works (EXCLUDED)
15. Provide necessary Lifting Equipment & Scaffolds for installation.
16. Testing & Commissioning of the above.

Excluding:

- 1) Dismantling of racking if needed or shifting of any stored materials.
- 2) Electrical works.
- 3) Anything not mentioned clearly.

Warranty: 400 days only

Lump Sum Price for above scope= 930,000 Q.R.

Delivery Time: 6-8 weeks from advanced payment date & PTW

Offer Validity: This proposal is valid for 15 days

Payment Terms: 50% Advance along with PO
30% Against Delivery of Acs to Site
20% Upon Completion

Assuring you our professional cooperation

METRI ENGINEERING SERVICES W.L.L

Eng. Fayez 55572793

