



Ref: MES-Q-26-0714

Date: 14 July 2026

M/s. Al Shams Trading & Contracting W.L.L.

Tel: +974 4431 0080 | Fax: +974 4412 0528 | Mob: +974 7712 3086

Email: chris@al-shamsgroup.com

Attention: Mr. Chris Job – Business Development Manager

Subject: Quotation for HVAC & Ventilation Works – TANNOUR BEIRUT RESTAURANT, Madina Centrale Building No. 03, The Pearl Qatar

Reference Drawings: Arkan Engineering Consultant W.L.L. detailed design set U329-J1669 (Equipment Schedule D-M-AC-0001, AC Duct System D-M-AC-0100, Chilled Water System, Ventilation System, Hood Ventilation System & System Layout), Rev. R0, dated 10-06-2026.

Dear Mr. Chris,

We thank you for inviting Metri Engineering Services W.L.L. to quote for the above project. Further to our review of the detailed design drawings and equipment schedules, we are pleased to submit our technical and commercial offer for the supply, installation, testing and commissioning of the HVAC and ventilation systems as per the scope defined below.

SCOPE OF WORKS & COMMERCIAL OFFER

Item	Description of Works	Qty	Total Price (QAR)
1	Relocation/Modification of Existing Chilled Water Fan Coil Units, Relocation of CHW Piping & New Ductwork – dismantling, shifting and re-installation of four (4) existing ceiling-concealed ducted CHW fan coil units as per equipment schedule: FCU-01 & FCU-02 (1,225 CFM / 2.58 TR each – ex. MC-045) and FCU-03 & FCU-04 (1,500 CFM / 3.38 TR each – ex. MC-046). – Relocation and modification of chilled water piping to suit new FCU positions, complete with isolation valves, flexible connections, drain piping, re-insulation and vapour barrier reinstatement. – Fabrication and installation of new GI supply, return and fresh-air ductwork with thermal insulation, complete with supply/return ceiling diffusers, grilles, volume control dampers, fire dampers where necessary, access doors, flexible ducts, hangers and supports, as per drawing D-M-AC-0100. – Leak testing and re-commissioning of the relocated CHW circuits.	Lot	50,000.00
2	Supply & Installation of New DX-Ducted Split Units (MIDEA or CARRIER) – DX-FCU-01 / ACCU-01: ducted horizontal ceiling-concealed DX split unit, 4.9 kW total cooling, 476 CFM @ 50 Pa ESP, 240/1/50 – one (1) no. – DX-FCU-02 / ACCU-02: ducted horizontal ceiling-concealed DX split units, 14.7 kW total cooling each, 1,720 CFM @ 50 Pa ESP, 240/1/50 – two (2) nos. – Complete with insulated refrigerant piping, condensate drain piping, GI ductwork with insulation, diffusers/grilles, dampers, wired controllers, outdoor unit supports and interconnecting works as per drawings. – Fabrication and installation of new GI supply, return and fresh-air ductwork with thermal insulation, complete with supply/return ceiling diffusers, grilles, volume control dampers, fire dampers where necessary, access doors, flexible ducts, hangers and supports, as per drawing D-M-AC-0100. – Condenser selection rated for 46°C ambient entering air temperature.	3 Nos.	69,000.00

Item	Description of Works	Qty	Total Price (QAR)
3	Supply & Installation of Ventilation Fans with Ductworks (VORTICE, FREGO) – KEF-01: kitchen hood exhaust centrifugal fan, 10,925 CFM @ 750 Pa, 415/3/50, 2-hour fire rated (300°C) – one (1) no. – KMF-01: kitchen make-up air inline fan, 6,800 CFM @ 550 Pa, 415/3/50, equipped with filter section – one (1) no. – EXF-01: toilets area inline exhaust fan, 150 CFM @ 150 Pa, 240/1/50, 2-hour fire rated (300°C) – one (1) no. – Complete with kitchen exhaust ductwork, make-up air and Toilet ventilation GI ductwork, backdraft dampers, fire dampers, VCDs, grilles, weather louvres, access doors, insulation/cladding where applicable, hangers and supports, as per hood ventilation and ventilation system drawings.	3 Nos.	114,825.00
4	Supply & Installation of Ventilating Ecology Unit + Ozone Generator + Air Curtain – ECU-01: kitchen hood exhaust ecology unit, 6,800 CFM, 240/1/50, 2-hour fire rated (300°C), c/w washable aluminium wire-mesh pre-filter, electrostatic filter and carbon filter cannister (600 mm depth) and ozone generation system – one (1) no. – OZONE-01: kitchen ozone-ceramic plate ozone generator, 200–350 W, 240/1/50, approx. 18 kg – one (1) no. – A.C-01: air curtain, 1.0 m length, 250 W, 240/1/50 – one (1) no. – Complete with connection ductworks, supports, and integration with the kitchen hood exhaust system.	Lot	55,000.00
5	Testing & Commissioning – Testing, adjusting and balancing (TAB) of air and water systems, functional testing of all installed equipment, and commissioning of the complete HVAC and ventilation installation with handover documentation.	Lot	Included
TOTAL CONTRACT PRICE (Items 1 – 5)			QAR 288,825.00

Amount in words: *Qatari Riyals Two Hundred Eighty-Eight Thousand Eight Hundred Twenty-Five Only (QAR 288,825/-).*

PAYMENT TERMS

- 50% Advance payment along with the Purchase Order / Letter of Intent.
- 30% Against supply of equipment to site.
- 20% Against completion of Testing & Commissioning.

TERMS & CONDITIONS

- Completion Period: 8 – 10 weeks from receipt of advance payment and site readiness, subject to equipment delivery schedules.
- Validity of Offer: 5 days from the date of this quotation.
- Warranty: 12 months on supplied equipment and workmanship from the date of handover, against manufacturing defects (excluding consumables and misuse).
- AC Equipment: MIDEA or CARRIER. FANS : VORTICE, Ecology unit : FREGO
- Working hours: normal day shift; any night/weekend working required by mall/UDC regulations to be coordinated by the client.
- Prices are in Qatari Riyals and exclusive of any applicable taxes or duties imposed after the date of this offer.

EXCLUSIONS

- Civil, builder's and finishing works (ceiling opening/closing, coring, painting, gypsum reinstatement).
- Electrical power supply cabling, isolators and DB modifications up to unit isolators (by others); our scope covers control wiring and final connections from isolators only.
- Kitchen hoods, fire suppression systems, gas detection and BMS integration, unless specifically stated above.
- UDC / The Pearl / authority permits, fees, deposits and approvals (documentation support will be provided).
- Any works not explicitly mentioned in the scope of works above.

We trust the above offer meets your requirements and we remain at your disposal for any technical or commercial clarification. We look forward to your valued Purchase Order.

Yours faithfully,

For Metri Engineering Services W.L.L.



Eng. Fayez Metri (55572793)