**Our Ref: MES/QDB/CHW/26-001** **Date: 16th March 2026**

**To:**
**AKHIL**
Sales Executive
Auriga Trading WLL
Website: www.aurigatradingco.com
Tel: +974 51775199 | +974 55868351

**Project:** QDB

## Subject: Chilled Water Flushing & Chemical Treatment

Dear Sir,

Further to your enquiry, please find below our offer.

### System Details

**No. of Circuits:** 2 Nos

**Circuit / Building 1**
Total Chilled Water Volume: 38 m³
No. of Chillers: 4 Nos
No. of FCUs: 5 Nos
No. of AHUs: 17 Nos

**Circuit / Building 2**
Total Chilled Water Volume: 35 m³
No. of Chillers: 3 Nos
No. of FCUs: 161 Nos
No. of AHUs: 4 Nos

### Details of Our Scope of Work

- Flushing of pipe networks using existing system pumps
- Supply of make-up water pump
- Supply of flushing and initial treatment chemicals
- Technical services until flushing completion
- Filters will be used to enhance the flushing operation
- Chemist will carry out chemical analysis at different stages of flushing
- A sample will be sent to ASHGHAL approved 3rd party laboratory after the operation, for their analysis and report (1 report per circuit, total of 2 reports)

**INCLUDED IN SCOPE:**

- Arrangement of continuous supply of fresh water into the system and discharge of waste water out of the system to meet the site flushing requirement.
- Drain points with valves at all the lowest points in the circuit
- Air vents & pressure gauges at all the highest points in the circuit
- connections to connect the filter and make pump (minimum 25mm).
- 6-8 laborers/manpower including HVAC SUPERVISOR are INCLUDED to start your system pumps, operation/handling any equipment in your system.
- Operation/handling of your equipment (Chillers, AHUs, FCUs, Heat Exchangers etc.)
- Scaffolding, lighting (for night operation) will be provided if required.
- Power source & cable for electric flushing pump.
- Site Access / Gate Permit. Will be coordinated with client.

## Parameters to be Followed

| Parameter | Value |
|---|---|
| pH | 9.0 - 10.5 |
| Conductivity (µ siemens/cm) | Max. 3000 |
| TDS (ppm) | Max. 2000 |
| Dissolved Iron (ppm as Fe) | Max. 0.5 |
| Nitrite $NaNO_2$ (ppm) | 800 - 1000 |

## Price

Our lump sum price for providing/carrying out the flushing operation is **QR 144,600/-**

**(QR 72,300/- per building)**

- *We have considered that the flushing of each circuit will be done in 10-11 days. Any additional days with no fault of ours will be charged at **QR 2,600 per day.***

## Exclusions

- Any work other than quoted in the offer
- Rectifying any leakage in the CHW system. It will be quoted case by case, also in case during flushing any leakage found it will be reported and quoted separately as the pipes are old and rusted so it will be quoted separately for rectification.
- Any liquidated damages
- Site office and stores
- Dosing equipment

**Note:** 2 weeks prior notice is required after the purchase order to start the work.

**Payment Terms**

- 60% advance
- Remaining 40% pro-rata basis payment. Shall be made on completion of each circuit, prior to submission of test reports.

We now look forward to receive your valuable order.

Thanks & Best Regards,

**Engr. Fayez Metri**
**Metri Engineering Services W.L.L.**
Mob: +974 555 72793