



**METRI ENGINEERING SERVICES W.L.L.**  
**مترى للخدمات الهندسية ذ.م.م**

## **TECHNICAL & COMMERCIAL PROPOSAL**

*for the*

**Turnkey Engineering, Procurement, Installation and  
Commissioning (EPIC) of HVAC Upgrade and Replacement**

Submitted to:

**QATAR FUEL ADDITIVES COMPANY LIMITED (QAFAC)**

Mesaieed Industrial City, Qatar

Submitted by:

**METRI ENGINEERING SERVICES W.L.L. (MES)**

|                    |                                    |
|--------------------|------------------------------------|
| Document Reference | MES / QAFAC / HVAC-EPIC / 2026-132 |
| Submission Date    | 07 June 2026                       |
| Revision           | 3                                  |



## **TABLE OF CONTENTS**

---

1. Executive Summary
2. Understanding of the Project
3. Technical Approach
4. Proposed Equipment & Specifications
5. Scope of Work – Inclusions
6. Scope of Work – Exclusions
7. Execution Methodology
8. Project Schedule
9. Quality Assurance & HSE
10. Commercial Proposal
11. Terms & Conditions



## 1. EXECUTIVE SUMMARY

---

Metri Engineering Services (MES) is pleased to submit this Technical and Commercial Proposal for the Turnkey Engineering, Procurement, Installation and Commissioning (EPIC) of HVAC Upgrade and Replacement at the QAFAC Methanol/MTBE Facility, Mesaieed Industrial City, Qatar.

This proposal addresses QAFAC's requirement to phase out R-22 refrigerant systems in compliance with the Montreal Protocol and Kigali Amendment, replacing them with environmentally friendly, low-GWP refrigerant systems. The equipment selection, specifications and quantities in this revision have been aligned to the latest manufacturer offer and to the tender clarifications issued under Bulletin No. 01 (Tender QTC/008/26).

### 1.1 Project Highlights

- Full replacement of R-22 systems across 8 buildings/locations, comprising 16 new units in total: 8 packaged AC units, 3 ducted-split (ACCU + AHU) systems, and 5 dedicated fresh-air units.
- A2L low-GWP refrigerant (R-454B) throughout, meeting ASHRAE 15/34 safety requirements (GWP 466, ODP 0).
- Equipment selected at 50°C ambient, with delivered capacities exceeding the revised building loads (typically +3% to +18% margin per the manufacturer selection).
- Petrochemical-grade construction: SS 316L casing and evaporator panels, Heresite-coated condenser and evaporator coils, 2-layer electrostatic powder paint (120 micron total), and NEMA 4X control panels.
- 3-wire system without neutral, with air-flow switch and dial gauge across each filter on every unit.
- Dedicated fresh-air units provided per building per Bulletin No. 01.
- Substation-4 and Substation-5 each fitted with two (2) packaged units; the General Services Building with two (2) packaged units, per the confirmed as-built configuration.
- Phased execution minimizing operational disruption, with temporary cooling solutions during replacement.
- Comprehensive turnkey delivery: design, supply, installation, commissioning, training and warranty.

### 1.2 MES Qualifications

MES brings extensive experience in industrial HVAC projects within Qatar's petrochemical sector, including work with QatarEnergy facilities and major industrial clients. Our team is certified for handling A2L refrigerants and hazardous material disposal, with proven capability in executing multi-phase turnkey contracts under strict HSSE requirements.

## 2. UNDERSTANDING OF THE PROJECT

---

### 2.1 Project Background

Qatar Fuel Additives Company (QAFAC) operates a major petrochemical facility in Mesaieed Industrial City producing approximately 3,000 MTPD of Methanol and 1,830 MTPD of MTBE. As part of QAFAC's commitment to environmental responsibility and regulatory compliance, this HVAC upgrade project addresses:

- Montreal Protocol mandate for R-22 refrigerant phase-out
- Requirements for low-GWP refrigerant transition
- QatarEnergy compliance
- Operational excellence through modern, efficient HVAC systems

### 2.2 Facilities Covered



The project encompasses HVAC replacement across the following buildings/locations. Quantities reflect the confirmed as-built configuration and Bulletin No. 01 clarifications:

| S/N | Building / Location             | Equipment Type               | Units         | Status           |
|-----|---------------------------------|------------------------------|---------------|------------------|
| 1   | HYPO Building (ME-5201 Shelter) | Packaged AC + Fresh-air unit | 1 PAC + 1 FAU | Full Replacement |
| 2   | Guard House                     | Packaged AC + Fresh-air unit | 1 PAC + 1 FAU | Full Replacement |
| 3   | Substation-4                    | Packaged AC + Chemical FAU   | 2 PAC + 1 FAU | Full Replacement |
| 4   | Substation-5                    | Packaged AC + Chemical FAU   | 2 PAC + 1 FAU | Full Replacement |
| 5   | Maintenance Workshop #1         | ACCU + AHU (ducted split)    | 1 set         | Full Replacement |
| 6   | Maintenance Workshop #2         | ACCU + AHU (ducted split)    | 1 set         | Full Replacement |
| 7   | Firehall Building               | ACCU + AHU (ducted split)    | 1 set         | Full Replacement |
| 8   | General Services Building       | Packaged AC + Fresh-air unit | 2 PAC + 1 FAU | Full Replacement |

**Note:** The Utility Lab packaged unit included in the previous revision is not part of the current manufacturer equipment schedule and has been removed pending QAFAC confirmation (see Section 4.3). Existing fresh-air ducts will be tied in to the new fresh-air units at the existing tie-in points; existing control panels, control/power cables and isolators will be reused where compatible. Temporary AC arrangements shall be provided during the replacement phase.

### 3. TECHNICAL APPROACH

#### 3.1 Design Philosophy

Our design approach ensures full compliance with QAFAC specifications while maximizing system reliability, energy efficiency and operational flexibility.

##### 3.1.1 Environmental Design Conditions

| Parameter                          | Design Value                                    |
|------------------------------------|-------------------------------------------------|
| Outdoor Design Ambient Temperature | 50°C Dry Bulb (equipment selection basis)       |
| Design Capacity Margin             | Delivered capacity $\geq$ revised building load |
| Indoor Design Temperature          | 24°C $\pm$ 2°C (as per space requirements)      |
| Relative Humidity                  | 50% $\pm$ 5% (for conditioned spaces)           |

##### 3.1.2 Refrigerant Selection

In compliance with the Montreal Protocol, Kigali Amendment and client requirements, all units are supplied with A2L (mildly flammable) low-GWP refrigerant R-454B:

| Refrigerant       | GWP | Safety Class | ODP |
|-------------------|-----|--------------|-----|
| R-454B (Proposed) | 466 | A2L          | 0   |



| Refrigerant                  | GWP   | Safety Class | ODP   |
|------------------------------|-------|--------------|-------|
| R-22 (Existing – Phased Out) | 1,810 | A1           | 0.055 |

Final refrigerant charge and safety provisions will be confirmed during detailed engineering based on ASHRAE 15/34 requirements for the specific building volumes.

### 3.1.3 Equipment Construction Standards

Construction is upgraded to petrochemical (corrosive-environment) grade in line with the manufacturer offer and Bulletin No. 01:

- **Casing / Enclosure:** Stainless Steel SS 316L
- **Evaporator Section:** SS 316L single-skin (packaged units); double-skin 2.0" injected-foam with SS 316L outer skin (AHUs)
- **Paint System:** 2-layer electrostatic powder paint, 120 micron total (C5-equivalent corrosion protection)
- **Coil Protection:** Heresite-coated copper-tube / aluminium-fin condenser and evaporator coils
- **Control Panel:** NEMA 4X
- **Unit Base:** Folded galvanised steel with 2-layer paint
- **Instrumentation:** Air-flow switch and dial gauge across each filter
- **Electrical:** 3-wire system without neutral; 415V – 3Ph – 50Hz
- **Motors:** High-efficiency, Class-H insulation, Temperature Rise Class B
- **Design Life:** Minimum 15 years

## 4. PROPOSED EQUIPMENT & SPECIFICATIONS

### 4.1 Packaged & Ducted-Split Unit Schedule

The following equipment is proposed (**manufacturer: PETRA, Jordan**), selected at 50°C ambient against the revised building loads. Capacities shown are delivered (calculated) with the required load in brackets; electrical data per the manufacturer AutoDesign output.

| Building           | Ref.           | PETRA Model          | Qty | Air L/s | Cooling kW<br>(del / req) | Comp.<br>kW | MCA / MOP (A) |
|--------------------|----------------|----------------------|-----|---------|---------------------------|-------------|---------------|
| Substation-4       | PAC-04         | PPHb-230             | 2   | 2800    | 63.5 / 54.1               | 20.6        | 54.7 / 70     |
| Substation-5       | PAC-05         | PPHb-175-2           | 2   | 1800    | 47.7 / 44.9               | 15.0        | 44.9 / 60     |
| Guard House        | PAC-GH-001     | PPHb-230             | 1   | 2200    | 59.0 / 51.8               | 20.4        | 54.7 / 70     |
| General Services   | PAC-Gen. Serv. | PPHb-360             | 2   | 3492    | 83.4 / 81.4               | 29.0        | 89.0 / 110    |
| HYPO (ME-5201)     | PAC-59-001     | PPHb-400             | 1   | 4147    | 98.0 / 95.5               | 33.2        | 98.6 / 125    |
| Maint. Workshop #1 | ACCU-01M       | DSPb-360 + PAHHC 80  | 1   | 3500    | 85.7 / 81.6               | 28.8        | 77.1 / 100    |
| Maint. Workshop #2 | ACCU-02M       | DSPb-450 + PAHHC 100 | 1   | 4500    | 105.5 / 103.5             | 33.6        | 82.5 / 110    |



| Building          | Ref.    | PETRA Model          | Qty | Air L/s | Cooling kW<br>(del / req) | Comp.<br>kW | MCA / MOP (A) |
|-------------------|---------|----------------------|-----|---------|---------------------------|-------------|---------------|
| Firehall Building | ACCU-FR | DSPb-530 + PAHHC 100 | 1   | 4500    | 133.7 / 133.0             | 48.3        | 104.3 / 125   |

**Notes:** All units R-454B, 415V/3Ph/50Hz. For the ducted-split systems the MCA/MOP shown is for the condensing unit (ACCU); the matching AHU fans (PAHHC 80/100) draw MCA 13.8–16.9 A (MOP 20–30 A). Substation-4, Substation-5 and General Services figures are per single unit (2 units each).

#### 4.2 Fresh-Air Unit Schedule (Item 3)

Dedicated fresh-air units (single-skin/double-skin SS 316L, 2-layer 120-micron paint) are provided per building, each with inlet/supply dampers (on/off actuator), SS 316L sand-trap louver, flat (EU-4) + bag (EU-8) filters and supply fan section:

| Building         | Model    | Qty | Air L/s | Fan Motor kW | Filtration / Notes            |
|------------------|----------|-----|---------|--------------|-------------------------------|
| Substation-4     | PAHHC 12 | 1   | 233     | 0.55         | Standard fresh-air filtration |
| Substation-5     | PAHHC 12 | 1   | 251     | 0.55         | Standard fresh-air filtration |
| Guard House      | PAHHC 12 | 1   | 327     | 0.75         | Standard fresh-air filtration |
| General Services | PAHHC 12 | 1   | 524     | 1.10         | Standard fresh-air filtration |
| HYPO (ME-5201)   | PAHHC 12 | 1   | 223     | 0.55         | Standard fresh-air filtration |

**Note on chemical filtration:** Per Bulletin No. 01 (item 14), the Substation-4 and Substation-5 fresh-air units shall incorporate chemical filtration media suitable for a methanol plant. The base manufacturer offer lists these as standard fresh-air units (sand-trap louver + bag filter); the gas-phase chemical filter media is carried as part of MES's scope and is reflected in the commercial pricing. Single fan per unit (no duty/standby) per QAFAC clarification.

#### 4.3 Manufacturer & Compliance Notes

**Proposed Manufacturer:** PETRA Air Conditioning Equipment Co. (Petra International Export Co. Ltd.), Amman – Jordan.

**Country-of-origin (Bulletin No. 01, item 1):** QAFAC has stated a preference for units originating from US/European manufacturers, and that units manufactured in Jordan or other Middle East countries shall not be submitted as the main offer and may be included only as an optional alternative subject to QAFAC review and approval. This PETRA (Jordan) offer is therefore submitted as MES's optional/alternative supply, fully compliant with the specified technical requirements; an alternative US/European-origin main offer can be developed on request.



## 5. SCOPE OF WORK – INCLUSIONS

---

MES's turnkey scope includes the following comprehensive deliverables:

### 5.1 Design Engineering & Planning

- Comprehensive site surveys of all buildings/locations
- Equipment sizing and selection at 50°C ambient against revised building loads
- Detailed HVAC system design incorporating A2L refrigerant safety requirements per ASHRAE 15/34
- Verification and validation of existing electrical infrastructure adequacy (MCC breakers, isolators, control wiring)
- Phase-wise execution plans aligned with QAFAC's long-term HVAC upgrade roadmap
- Temporary cooling design and planning for each building replacement phase
- Preparation of layouts, calculations and design reports

### 5.2 Equipment Procurement & Logistics

- Supply of new PACs, AHUs, ACCUs and fresh-air units with low-GWP refrigerants
- Factory testing and inspection
- International freight, customs clearance and delivery to QAFAC Mesaieed site
- Proper storage and preservation per OEM guidelines

### 5.3 Temporary Cooling Solutions

- Packaged AC units with ducting and controls during equipment replacement
- Temporary electrical arrangements and power supplies
- Qualified operators to maintain temporary units until permanent systems commissioned

### 5.4 Dismantling & Safe Disposal

- Safe dismantling of existing R-22 units, refrigerant lines and electrical connections
- R-22 refrigerant recovery and environmentally compliant disposal per Qatar environmental standards
- Removal of accessories and debris with proper waste management

### 5.5 Installation & Construction

- Installation of new HVAC units (PACs, AHUs, ACCUs, fresh-air units) with duct modifications to the existing duct network
- Tie-in of fresh-air units to existing fresh-air ducts at the available tie-in points (additional ductwork if required by Contractor)
- New refrigerant piping and insulation
- Electrical power and control cabling with supports
- Cable trays, pull boxes, isolators and ducting modifications as required
- Replacement of undersized MCCBs, isolators and wiring modifications where required
- Utilizing the existing civil and structural foundations (platforms, supports, foundations)
- New aluminium cladding for external ducts, pipes and refrigerant lines
- Restoration works (plastering, cladding, ceiling finishes) where required

### 5.6 Testing & Commissioning

- Pressure testing, vacuum testing, leak testing and refrigerant charging
- Electrical, mechanical and control function testing
- Performance verification and air balancing (including the 4 buildings specified in the clarifications)
- Commissioning test reports and start-up logs

### 5.7 Documentation & Handover

- Engineering design calculations and drawings
- As-built drawings
- Warranty certificates
- Operation & Maintenance (O&M) manuals
- Recommended spare parts list (2 years)

### 5.8 Training

- 3 days end-user training split between two batches
- Hands-on training for A2L refrigerant handling and safety procedures
- O&M training for new equipment

### 5.9 Warranty & Support

- 12-month comprehensive warranty post-commissioning for each unit
- On-call support for faults and breakdowns during warranty period

## 6. SCOPE OF WORK – EXCLUSIONS

---

The following items are excluded from MES's scope unless specifically agreed otherwise:

### 6.1 Client Responsibilities (QAFAC)

- Site access permissions, gate passes, trainings, security clearances and their associated costs
- PTW (Permit to Work) processing and approvals
- Coordination with plant operations for building shutdowns
- Power isolation and lockout/tagout procedures
- Safety induction for contractor personnel (provided by QAFAC)
- Review and approval of design documents and MOC submissions

### 6.2 Infrastructure Exclusions

- Upgrades to main power distribution panels or transformers
- Main building electrical infrastructure modifications beyond local MCC/isolator level
- BMS/SCADA system modifications & integration (by specialist system integrator)
- Fire alarm system modifications & integration (by specialist system integrator)
- Structural reinforcement beyond equipment mounting requirements

### 6.3 Other Exclusions

- Replacement or modification of existing fresh-air ducts beyond the new fresh-air unit tie-ins
- Existing ductwork replacement (unless defective parts found during site survey)





- Post-warranty maintenance services (available separately)
- Asbestos or hazardous material abatement (if discovered)
- Costs arising from unforeseen site conditions not visible during site survey

## 7. EXECUTION METHODOLOGY

---

### 7.1 Project Phases

The project will be executed in the following phases to ensure minimal disruption to plant operations:

| Phase   | Activities                                                      | Duration    |
|---------|-----------------------------------------------------------------|-------------|
| Phase 1 | Mobilization, Site Survey, Detailed Engineering, MOC Submission | 6–8 weeks   |
| Phase 2 | Equipment Procurement, Manufacturing                            | 12–14 weeks |
| Phase 3 | Delivery, Storage, Building-wise Installation                   | 4–6 weeks   |
| Phase 4 | Testing, Commissioning, Training, Handover                      | 2–4 weeks   |

**Note:** Outdoor installation works will be paused during summer months (June–September) unless permitted by QAFAC. The project timeline can span multiple execution windows if required.

### 7.2 Building-Wise Execution Strategy

- One building at a time approach to minimize operational impact
- Temporary cooling deployed before existing unit disconnection
- Pre-fabrication of ducts, piping, supports and cable trays to minimize on-site work duration
- Weekend/night-shift work available for critical areas (subject to PTW approval)

## 8. PROJECT SCHEDULE

---

**Estimated Overall Project Duration:** 24 weeks (excluding summer pause if applicable).

A detailed project schedule will be submitted within 2 weeks of contract award, incorporating:

- QAFAC building shutdown schedule coordination
- Equipment lead times from the selected manufacturer
- Summer pause accommodation (June–September)
- Site readiness and PTW availability

## 9. QUALITY ASSURANCE & HSE

---

### 9.1 Quality Management

MES maintains a quality management system. Key QA measures include:

- Inspection and Test Plans (ITP) for all critical activities
- Material and equipment certificates verification
- Site inspections and hold points
- Non-conformance reporting and corrective actions



## 9.2 Health, Safety & Environment

Full compliance with QAFAC HSSE requirements and PTW system, including:

- Job Hazard Analysis (JHA) for all work activities
- Method statements for critical activities
- Daily toolbox talks and safety briefings
- PPE provision for all personnel
- Medical fitness certificates for all workers
- Certified lifting equipment and personnel
- Environmental compliance for R-22 recovery and disposal
- Noise control and waste management procedures

## 9.3 Applicable Standards & Codes

| Standard / Code      | Application                              |
|----------------------|------------------------------------------|
| ASHRAE Standards     | HVAC design and application              |
| ASHRAE 15/34         | A2L refrigerant safety requirements      |
| NFPA 70 & 90A        | Electrical safety and ductwork           |
| IEC Standards        | Electrical works                         |
| QCS                  | Qatar Construction Specifications        |
| ISO 9001/14001/45001 | Contractor QMS, EMS, OH&S certifications |
| ISO 50001:2018       | Energy management requirements           |
| Montreal Protocol    | Refrigerant phase-out compliance         |
| Kigali Amendment     | Low-GWP refrigerant requirements         |



## 10. COMMERCIAL PROPOSAL

### 10.1 Bill of Quantities

Pricing is provided as a lump sum per tender requirements. The supply prices have been revised in direct proportion to the latest PETRA equipment offer (QAT/57719/5/1/2025), preserving MES's existing margin on each line; installation is taken at 50% of supply per building, consistent with the previous revision. A detailed breakdown is available in the attached BOQ spreadsheet.

| Item                                              | Description                                                                             | Qty | Unit | Rate (QAR) | Total (QAR) |
|---------------------------------------------------|-----------------------------------------------------------------------------------------|-----|------|------------|-------------|
| 1                                                 | Design and Engineering                                                                  | 1   | Lot  | 90,000     | 90,000      |
| <b>2. Supply and Delivery of Materials</b>        |                                                                                         |     |      |            |             |
| 2.1                                               | HYPO Building (ME-5201 Shelter) – 1×PPHb-400 + 1×FAU                                    | 1   | Lot  | 413,020    | 413,020     |
| 2.2                                               | Guard House – 1×PPHb-230 + 1×FAU                                                        | 1   | Lot  | 240,023    | 240,023     |
| 2.3                                               | Substation-4 – 2×PPHb-230 + 1×Chemical FAU                                              | 1   | Lot  | 436,390    | 436,390     |
| 2.4                                               | Substation-5 – 2×PPHb-175-2 + 1×Chemical FAU                                            | 1   | Lot  | 435,651    | 435,651     |
| 2.5                                               | Maintenance Workshop #1 – ACCU-01M (DSPb-360 + PAHHC 80)                                | 1   | Lot  | 266,214    | 266,214     |
| 2.6                                               | Maintenance Workshop #2 – ACCU-02M (DSPb-450 + PAHHC 100)                               | 1   | Lot  | 372,007    | 372,007     |
| 2.7                                               | Firehall Building – ACCU-FR (DSPb-530 + PAHHC 100)                                      | 1   | Lot  | 393,892    | 393,892     |
| 2.8                                               | General Services Building – 2×PPHb-360 + 1×FAU                                          | 1   | Lot  | 607,897    | 607,897     |
|                                                   | Utility Lab – excluded this revision (no manufacturer unit; pending QAFAC confirmation) | —   | —    | Excluded   | 0           |
| 3                                                 | Supply and Installation of Temporary Cooling Units                                      | 1   | Lot  | 240,000    | 240,000     |
| <b>4. Installation, Testing and Commissioning</b> |                                                                                         |     |      |            |             |
| 4.1                                               | HYPO Building (ME-5201 Shelter)                                                         | 1   | Lot  | 206,510    | 206,510     |
| 4.2                                               | Guard House                                                                             | 1   | Lot  | 120,012    | 120,012     |
| 4.3                                               | Substation-4                                                                            | 1   | Lot  | 218,195    | 218,195     |
| 4.4                                               | Substation-5                                                                            | 1   | Lot  | 217,826    | 217,826     |
| 4.5                                               | Maintenance Workshop #1                                                                 | 1   | Lot  | 133,107    | 133,107     |
| 4.6                                               | Maintenance Workshop #2                                                                 | 1   | Lot  | 186,004    | 186,004     |
| 4.7                                               | Firehall Building                                                                       | 1   | Lot  | 196,946    | 196,946     |
| 4.8                                               | General Services Building                                                               | 1   | Lot  | 303,949    | 303,949     |



| Item                                                       | Description                                          | Qty | Unit | Rate (QAR) | Total (QAR)      |
|------------------------------------------------------------|------------------------------------------------------|-----|------|------------|------------------|
| 5                                                          | O&M Training and Handling of New Refrigerants        | 1   | Lot  | 30,000     | 30,000           |
| 6                                                          | Dismantling and Safe Disposal of Existing R-22 Units | 1   | Lot  | 42,000     | 42,000           |
| 7                                                          | Documentation and Handover                           | 1   | Lot  | 12,000     | 12,000           |
| <b>TOTAL PRICE (QAR)</b>                                   |                                                      |     |      |            | <b>5,161,643</b> |
| <b>Price increase adjustment due to current conditions</b> |                                                      |     |      |            | <b>253,780</b>   |
| <b>TOTAL PRICE (QAR)</b>                                   |                                                      |     |      |            | <b>5,415,423</b> |

\*\* Utility Lab was a priced line in the previous revision; it is excluded here because the latest manufacturer schedule contains no corresponding unit. The General Services Building, previously shown as nil (no tender detail), is now priced against the confirmed 2×PPHb-360 selection.

## 10.2 Pricing Notes

- All prices include applicable taxes, duties and fees
- Prices include overhead costs, profit, administrative expenses, utilities, workmen compensation policy and indirect expenses
- All direct costs included (materials, labour, machinery)
- Documentation and reporting costs included (as-built drawings, test reports, JHA, method statements)
- Delivery, shipping and transportation to QAFAC Mesaieed Plant included
- All required PPE
- Supply prices revised in proportion to PETRA Quotation QAT/57719/5/1/2025; lump-sum items (design, temporary cooling, training, disposal, documentation) carried forward unchanged from the previous revision
- Excluding any gate pass, any medical fitness, any specialized training for QE. Any costs/processing costs etc to any trainings or permits or passes.

## 10.3 Payment Terms

MES proposes the following milestone-based payment schedule:

| Milestone | Description                              | % of Contract |
|-----------|------------------------------------------|---------------|
| 1         | Contract Award / Mobilization Advance    | 50%           |
| 2         | Design Approval / Equipment Order        | 20%           |
| 3         | Equipment Delivery to Site               | 15%           |
| 4         | Installation Complete (per building)     | 10%           |
| 5         | Final Commissioning, Training & Handover | 5%            |



## 11. TERMS & CONDITIONS

---

### 11.1 Proposal Validity

This proposal is valid for 15 days from the date of submission.

### 11.2 Contract Duration

As per QAFC project planning and site constraints, with accommodation for summer pause periods (June–September) unless specifically permitted.

### 11.3 Warranty Period

- 12-month comprehensive warranty for each unit, commencing from successful installation and commissioning (not delivery)
- On-call support for faults and breakdowns included during warranty period

### 11.4 Force Majeure

Standard force majeure provisions apply for events beyond reasonable control of either party.

### 11.5 Compliance

MES confirms full compliance with all QAFC HSSE requirements, PTW system and applicable Qatar regulations. All installations will comply with Recognized and Generally Accepted Good Engineering Practices.

Best Regards,

**METRI ENGINEERING SERVICES W.L.L.**

**Eng. Fayez Metri**

*Managing Director*

