| | | | |
|---|---|---|---|
| **To** | : ***M/s Ismail Bin Ali Trading & Contracting (IBA)*** | **From:** | **ENGR. METRI** |
| **Attn** | : **Engr. Abdelhai Aljamaliah** | **Mobile:** | **+974 5099 2089** |
| | | **E-mail:** | a.aljamaliah@iba.com.qa |
| **Date** | : 31 March, 2026 | **Pages:** | : 03 |

**Sub** : **Design, Supply & Installation of Walk In Cold Rooms** Ref. #: **MES/QTN/IBA/2026-0331**
**HOTEL & RESIDENTIAL APARTMENT TOWER (5B+G+38 FLOORS) — ONAIZA**

Dear Sir,

With reference to your inquiry dated 30 March 2026, we are pleased to submit our proposal for your above requirements to wit:

**SCOPE OF WORK** : Design, Supply, Installation, Testing & Commissioning of 3 no. Walk-in Cold Rooms as per below table.

| # | ROOM | w | d | h | Area m² | Vol m³ |
|---|---|---|---|---|---|---|
| 1 | Catery Chiller +2°C | 6.80 | 2.08 | 2.40 | 14.14 | 33.94 |
| 2 | Receiving Freezer -18°C | 3.25 | 2.08 | 2.40 | 6.76 | 16.22 |
| 3 | Receiving Chiller +2°C | 3.40 | 2.08 | 2.40 | 7.07 | 16.97 |
| | **TOTAL** | | | | **27.97** | **67.13** |

**Dimensions** : AS PER ABOVE
(PUR Wall & PUR Ceiling PANEL THICKNESS: **100mm for Chiller rooms, 150mm for Freezer room**)

**Doors** : 1 no. Single Leaf Hinged Door 0.8m x 1.8m with heater per room (3 nos. total)

**Floor Insulation** : PUR PANEL 100mm THICK and finished by aluminum checkered sheets ontop.

**Refrigeration Units** : Condensing Units made by BITZER OR EMERSON COPELAND, or DORIN ITALY with Matching Evaporator Units

**Sandwich Panel INSULATION** : PUR (POLYURETHANE) (Made in Qatar)
**THICKNESS** : **100mm for Chiller rooms (+2°C), 150mm for Freezer room (-18°C)**
**CLADDING** : **0.5 mm pre-painted GI sheets.**

**CONSTRUCTION** : Panels are joined together by means of tongue and groove and locked together on each side of the panel to ensure air tight joints.

**DOOR ACCESSORIES** : Door is complete with fittings and accessories and have the same finish and thickness as that of the walls and ceiling, complete with rubber gaskets, safety release handle.

**Lighting** : LED lights included to provide the appropriate light levels for each cold store.

**Ref. Accessories** : All accessories such as expansion valve, solenoid, sight glass, pressure relief valves …etc are included.

**CONTROL PANEL** : Specially designed to control & secure the system.
1 no. control panel for each cold room will be provided with necessary contactor, overload relay, signal lights…etc

**PIPES** : Copper pipes are made by Muller Brass or Equivalent.

**M/ ACCESSORIES** : Will be provided including rivets, internal and external flashing, silicon and hygienic plastic corners.

**Excluding** : **Electrical Power to be arranged by client at site & Any Civil Works.**

## TOTAL PRICE FOR ABOVE = 111,500 Q.R.

**PAYMENT TERMS** : 60% advance
20% upon delivery of cooling units
20% upon Completion

**DELIVERY** : 2-4 weeks from the date of your firm order along with the receipt of down payment provided the site is ready for installation.

**WARRANTY** : 1 year on all materials supplied and installed by MES + 1 YEAR ON COMPRESSOR ONLY + free preventive maintenance for the 1st year. Servicing other than MES authorized technician voids warranty.

**NOTE : All civil works and main power EXCLUDED. Our work is limited to the above quoted.**
*Delay of delivery due to acts of 3rd party (non-availability of supply); site readiness; accidents will not be accounted to MES. Warranty does not cover force majeure, loss due to fire or damage due to natural calamities. MES will not be held liable for any damage on products or items inside the cold room.*

**VALIDITY** : 10 days.
We trust the above quotation merits your attention and we look forward to serving your requirement soon. Should you need any further clarification, please do not hesitate to contact us.

Thanks & regards,

**Metri Engineering Services W.L.L**
**Eng. Fayez 55572793**

متري للخدمات الهندسية ذ.م.م
ص.ب: ١٩٩٦٢ الدوحة - قطر
تليفكس: ٤٤١٢٧٦٧
P.O. Box 19962, Doha-Qatar
TelFax: 4412767
METRI ENGINEERING SERVICES W.L.L