

### QUOTATION

**Quotation Ref:** MES/QTN/2026/388

**Project:** Chiller & Freezer Room Refrigeration

**Date:** 17 June 2026

**Validity:** 5 days from date above

**To:**

#### **Supreme Supply and Services**

Salwa Industrial Area, Al Nayeef Souq, 2nd Floor, Office No. 248

Doha, Qatar

Attn: Mr. M A N Prasad – Sales & Operations Manager

Mobile: +974 5588 4987 | Email: prasad@supremeqatar.com

**Subject:** Installation, Testing & Commissioning of Refrigeration Equipment for Chiller and Freezer Rooms (client-supplied equipment).

Dear Mr. Prasad,

Thank you for the opportunity to quote. With reference to your enquiry, we are pleased to submit our offer for the installation, testing and commissioning of the refrigeration equipment supplied by your good office, as detailed below. Our scope, exclusions and commercial terms are set out in the following sections.

#### **1. Equipment Schedule (Supplied by Client)**

| Sr. | Room                                                                          | Description                                                                                                                               | UOM | Qty |
|-----|-------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------|-----|-----|
| 1   | <b>Chiller Room</b><br>4.24 × 2.72 × 2.45 m<br>(external)<br>Temp: +3 ~ -3 °C | <b>Condensing Unit – Original Copeland Brand</b><br>Model: ZX020BE   2 HP<br>Voltage: 380V / 50Hz / 3Ph<br>Refrigerant: R-404a (no fill)  | SET | 1   |
| 2   |                                                                               | <b>Evaporator – Model VCS45 0052L-35E2T1</b><br>Cooling capacity: 5.2 kW<br>Fan motor: 2 × 350 mm<br>Voltage: 380V / 50Hz / 3Ph           | SET | 1   |
| 3   | <b>Freezer Room</b><br>4.24 × 2.72 × 2.45 m<br>(external)<br>Temp: -18 °C     | <b>Condensing Unit – Original Copeland Brand</b><br>Model: ZXL030BE   3 HP<br>Voltage: 380V / 50Hz / 3Ph<br>Refrigerant: R-404a (no fill) | SET | 1   |
| 4   |                                                                               | <b>Evaporator – Model VCS60 0060D-40E2T1</b><br>Cooling capacity: 6.0 kW<br>Fan motor: 2 × 400 mm<br>Voltage: 380V / 50Hz / 3Ph           | SET | 1   |

*Note: All equipment above is supplied by the client. MES scope covers installation works only as detailed in Section 2.*

#### **2. Scope of Work**

1. Installation, testing and commissioning of the above client-supplied refrigeration equipment.
2. Supply and installation of necessary refrigerant copper pipes with insulation.
3. Supply and installation of control panel.
4. Supply and installation of steel support stand or pre-cast concrete base for the outdoor (condensing) units.
5. Testing and commissioning of the complete installation.

### 3. Commercial Offer

| Description                                                                                                                                                                                                                                                                                                                                                    | Amount (QAR)     |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|
| Installation, testing and commissioning of client-supplied refrigeration equipment for the Chiller and Freezer rooms — inclusive of refrigerant copper piping with insulation, supply & installation of control panel, steel support stand / pre-cast concrete base for the outdoor units, and full testing & commissioning (as per Scope of Work, Section 2). | 11,600.00        |
| <b>TOTAL (Lump Sum)</b>                                                                                                                                                                                                                                                                                                                                        | <b>11,600.00</b> |

Amount in words: Qatari Riyals Eleven Thousand Six Hundred Only.

### 4. Exclusions

1. Electrical power supply and isolator.
2. Drain point – to be provided by the client near the equipment.
3. Supply of refrigeration equipment (condensing units and evaporators), refrigerant gas charge, civil/builder's work, and any item not expressly listed under Scope of Work.

### 5. Commercial Terms & Conditions

1. Prices are in Qatari Riyals (QAR) and exclusive of any applicable taxes/fees.
2. Payment terms: 50% advance with purchase order, balance 50% on completion and handover.
3. Delivery / completion period: to be mutually agreed upon receipt of confirmed order and site readiness.
4. This offer is valid for 5 days from the quotation date.
5. Works to be executed during normal working hours; site access, storage and a safe working area to be provided by the client.
6. Any variation in scope shall be quoted and agreed separately prior to execution.

We trust the above meets your requirements and look forward to your valued confirmation. Should you require any clarification, please do not hesitate to contact us.

For and on behalf of

**Metri Engineering Services W.L.L.**

