

TECHNICAL & COMMERCIAL QUOTATION

Supply, Installation, Testing & Commissioning of Growth Chamber (Chiller Room) and Freezer Room

Quotation No.	MES/QTN/2026-08/55	Date	14 August 2026
Client	MedTech Corporation, P.O. Box 30647, Doha – Qatar	Your Ref.	RFQ e-mail dated 12 August 2026
Attention	Ms. Shalomi Rachchel – Sales Specialist, Life Science & Informatics	Copy To	Life Science Dept. / Mr. Ovais ur Rehman
Project	Ministry of Qatar – Growth Chamber & Freezer Room	Validity	60 days from date of issue

Dear Ms. Shalomi,

Thank you for your enquiry dated 12 August 2026 and for the opportunity to quote for the above Ministry of Qatar project. We confirm that the required scope is fully within our capability, and we are pleased to submit our technical and commercial offer for the supply, installation, testing and commissioning of one (1) Chiller Room / Growth Chamber and one (1) Freezer Room.

Our offer follows your specification in all material respects. Refrigeration is offered with DORIN or EMERSON COPELAND semi-hermetic condensing units with matching THERMOWAY or equivalent evaporators, and the cold-room sandwich panels JMB Qatar sandwich panels. For the growth chamber, dedicated humidification and dehumidification equipment has been included so that relative humidity is actively controlled across the full 0°C to +28°C operating band.

1. CHILLER ROOM – GROWTH CHAMBER (0°C to +28°C)

External Dimensions	3000 mm (W) x 5000 mm (L) x 3000 mm (H) – external.
Operating Temperature	Adjustable growth-chamber range 0°C to +28°C.
Refrigerant	R404A.
Condensing Units	2 Nos. 3 HP semi-hermetic air-cooled condensing units, DORIN (Italy) Model AUH 301 CC or equivalent EMERSON COPELAND semi-hermetic unit. Rated capacity 2.2 kW each; 3 Phase / 50 Hz.
Evaporators	2 Nos. matching THERMOWAY unit coolers, selected to suit the room load and the full 0°C to +28°C operating band. Complete with fans, electric defrost, drain pan and heated drain line
Humidity Control	Relative humidity fully controlled up to 100% RH. Supply and installation of a dedicated humidifier complete with distribution manifold, water feed and drain connections. Supply and installation of a dedicated refrigerant-type dehumidifier for humidity reduction and dew-point control. Both units interlocked to the room control panel through an electronic humidistat / humidity controller for automatic modulating control of the set-point.
Sandwich Panels	Sandwich panels manufactured by JMB Qatar. Insulation: rigid injected CFC-free polyurethane / PIR foam, overall density 40 – 45 kg/m ³ . Panel thickness: 100 mm. Cladding: 0.5 mm pre-painted GI sheets (ribbed) both faces, with nylon protective film. Construction: tongue-and-groove joints to ensure air-tight joints. Fire rating: flame retardancy to DIN 4102 Class B3, tested to ASTM D 1692 and ISO 3582 (self-extinguishing foam); total panel B2 classified.

Doors	2 Nos. hinged doors complete with rubber gasket and all accessories. 40 kg/m ³ polyisocyanurate (PIR), fire class B s1d0 to TS EN 13501-1. 100 mm thickness, pre-painted finish, clear size 900 mm (W) x 1900 mm (H). Made in Turkey. Each door provided with PVC strip air curtain.
Floor Insulation	100 mm thick insulated floor panels reinforced with wooden spacers, overlaid with 12 mm WBP plywood and finished with non-slip chequered aluminium sheet.
Control Panel	Control panel apparatus and wiring suitable for 3 Phase / 50 Hz electrical supply; control circuit 415 V. Dixell digital microprocessor controllers (Italy) to monitor and regulate room temperature, defrost and defrost termination, fan delay and compressor run status.
Shelving	Internal shelving system for chamber contents.
Irrigation System	Fully automated and controlled irrigation system serving the growth chamber.
Lighting System	Growth lighting system in 3 different colors.
Camera System	Internal camera / monitoring system installed within the chamber.
Accessories	Rivets, internal and external flashing, silicone sealant, ceiling suspension system, refrigeration pipework and insulation, electrical wiring and containment, screws, nuts, steel bars, washers, rubber support suspensions, anchor bolts, threaded rods, LED lights and waterproof switches.
Works Included	Complete supply, delivery to site, offloading, panel erection, refrigeration pipework and interconnection, electrical interconnection from the control panel to all served equipment, evacuation and charging, testing, commissioning and handover.
Excluded	Main Electrical Cable supply till the control panel and Isolators. Main Water Supply

2. FREEZER ROOM (–20°C to –18°C)

External Dimensions	3000 mm (W) x 5000 mm (L) x 2400 mm (H) – external.
Operating Temperature	–20°C to –18°C.
Refrigerant	R404A.
Condensing Units	2 Nos. 4 HP semi-hermetic air-cooled condensing units, DORIN (Italy) Model AUH 405 CS or equivalent EMERSON COPELAND semi-hermetic unit. Rated capacity 3.1 kW each; 3 Phase / 50 Hz.
Evaporators	2 Nos. matching THERMOWAY unit coolers selected for low-temperature duty. Complete with fans, electric defrost, heated drain pan and drain line.
Sandwich Panels	Sandwich panels manufactured by JMB Qatar. Insulation: rigid injected CFC-free polyurethane / PIR foam, overall density 40 – 45 kg/m ³ . Panel thickness: 100 mm. Cladding: 0.5 mm pre-painted GI sheets (ribbed) both faces, with nylon protective film. Construction: tongue-and-groove joints to ensure air-tight joints. Fire rating: flame retardancy to DIN 4102 Class B3, tested to ASTM D 1692 and ISO 3582 (self-extinguishing foam); total panel B2 classified.
Doors	2 Nos. hinged doors complete with rubber gasket and all accessories. 40 kg/m ³ polyisocyanurate (PIR), fire class B s1d0 to TS EN 13501-1. 100 mm thickness, pre-painted finish, clear size 900 mm (W) x 1900 mm (H). Made in Turkey. Each door provided with PVC strip air curtain.
Floor Insulation	100 mm thick insulated floor panels reinforced with wooden spacers, overlaid with 12 mm WBP plywood and finished with non-slip chequered aluminium sheet.
Control Panel	Control panel apparatus and wiring suitable for 3 Phase / 50 Hz electrical supply; control circuit 415 V.

	Dixell digital microprocessor controllers (Italy) to monitor and regulate room temperature, defrost and defrost termination, fan delay and compressor run status.
Shelving	Internal shelving system for freezer contents.
Accessories	Rivets, internal and external flashing, silicone sealant, ceiling suspension system, refrigeration pipework and insulation, electrical wiring and containment, screws, nuts, steel bars, washers, rubber support suspensions, anchor bolts, threaded rods, LED lights and waterproof switches.
Works Included	Complete supply, delivery to site, offloading, panel erection, refrigeration pipework and interconnection, electrical interconnection from the control panel to all served equipment, evacuation and charging, testing, commissioning and handover.
Excluded	Main Electrical Cable supply till the control panel and Isolators. Main Water Supply

3. PRICE SCHEDULE

Item	Description	Qty	Amount (QAR)
1	Chiller Room – Growth Chamber (0°C to +28°C) Supply, installation, testing and commissioning as per Item 1 above, including humidifier and dehumidifier for full humidity control, irrigation system, 3-colour lighting and camera system.	1 Lot	130,000.00
2	Freezer Room (–20°C to –18°C) Supply, installation, testing and commissioning as per Item 2 above, including panels, doors, refrigeration units, control panels and shelving.	1 Lot	107,000.00
TOTAL QUOTED PRICE (QAR)			237,000.00
Amount in words: Qatari Riyals Two Hundred Thirty-Seven Thousand Only.			

All prices are in Qatari Riyals (QAR), quoted on a lump-sum basis, delivered and installed at site within the State of Qatar.

4. PAYMENT TERMS

Stage	Milestone	Amount (QAR)
50%	Advance payment against confirmed Purchase Order / LPO.	118,500.00
30%	Against delivery of equipment and panels to site.	71,100.00
20%	Against completion of works, commissioning and handover.	47,400.00

5. WARRANTY

- Two (2) years warranty on the refrigeration units.
- Two (2) years warranty on the compressors.
- One (1) year free service, covering scheduled preventive maintenance visits from the date of handover.
- Warranty covers manufacturing and workmanship defects under normal operating conditions. It excludes damage arising from misuse, unauthorized intervention, power supply irregularity, or operation outside the specified design conditions.

6. DELIVERY & COMPLETION

- Delivery of equipment and panels: approximately 6 – 8 weeks from receipt of a confirmed Purchase Order, advance payment and approved shop drawings / material submittals.
- Installation, testing and commissioning: approximately 3 – 4 weeks from delivery to site, subject to the works area being ready and free of obstruction.
- The above periods are indicative and subject to manufacturer confirmation at the time of order placement.

7. SCOPE CLARIFICATIONS & EXCLUSIONS

The following are excluded from our offer and shall be provided by others:

- All civil, builder's and finishing works, including floor screed, levelling and preparation of the slab to receive the cold rooms.
- Main power supply, distribution board, main power cabling and earthing up to the MES control panels; the works area shall be provided with adequate temporary power during installation.
- Water supply and drainage points required for the humidifier, dehumidifier and evaporator condensate drains, terminated at the equipment location.
- Network / IT infrastructure, recording server, storage and monitoring station for the camera system; our scope covers the in-room cameras and their connection points.
- Water source, storage tank and feed line for the irrigation system up to the room; our scope covers the in-room automated irrigation distribution and control.
- Craneage or specialized lifting for delivery to levels other than ground floor, and any hoisting through restricted openings.
- Authority approvals, permits, third-party inspections and any statutory fees.
- Works outside normal working hours, and any night-shift or holiday permits.
- Any item, service or modification not expressly stated in this quotation shall be treated as a variation and quoted separately.

8. GENERAL TERMS & CONDITIONS

- Quotation validity: 60 days from the date of issue.
- Prices are exclusive of any taxes, duties or levies that may be imposed by the authorities; if applicable, these shall be to the client's account.
- Equipment makes and models offered are as stated. Where an equivalent is offered, it shall be of equal or superior performance and submitted for approval prior to ordering.
- Final capacities and equipment selections shall be confirmed against the approved room construction, ambient design conditions and product loading at the time of order.
- Cancellation after order placement will be subject to recovery of all costs incurred, including restocking and cancellation charges levied by manufacturers.
- This quotation and any resulting order are governed by the laws of the State of Qatar.

We trust that our offer meets your requirements and that of the end user, and we remain at your disposal for any technical clarification or adjustment to the scope. We look forward to your valued order.

METRI ENGINEERING SERVICES W.L.L.

