

TECHNICAL & COMMERCIAL QUOTATION

Replacement of Cold-Room Refrigeration Units — Qatar Steel, Mesaieed Industrial City

Quotation Ref.: MES/QTN/2026/0416-01 Date: 16 April 2026 Project: Cold-Room Refrigeration Replacement Location: Qatar Steel, Mesaieed Industrial City (MIC)	Kind Attention: M/s EMCO QATAR Doha, State of Qatar <i>Re: Refrigeration System Replacement — Qatar Steel Cold-Room Facility, MIC</i>
--	--

INTRODUCTION

Dear Sirs,

Further to your enquiry and the site maintenance survey carried out at the Qatar Steel cold-room facility at Mesaieed Industrial City (MIC), we thank you for the opportunity to submit our offer for the replacement of the existing refrigeration units in five (5) rooms — four (4) chillers and one (1) freezer — including the conversion of Room No. 20 from a chiller to a freezer.

Our proposal covers supply, installation, testing and commissioning on a lump-sum turn-key basis in accordance with the scope detailed below and the attached site survey report.

SCOPE OF WORK — ROOM-WISE BREAKDOWN

The following works shall be executed for each of the rooms surveyed:

Room No.	Application	Dimensions (cm) L × W × H	Design Condition	Scope of Work
20	Chiller → Convert to Freezer	260 × 330 × 280	-18 °C to -20 °C	- Dismantle and dispose existing units - New refrigeration system (low-temp) - New control panel - New insulated cold-room door with heater frame (0.8 × 1.8 m) - New pressure relief device (PRD)
13	Freezer	260 × 330 × 280	-18 °C to -20 °C	- Dismantle and dispose existing units - New refrigeration system (low-temp) - New control panel

Room No.	Application	Dimensions (cm) L x W x H	Design Condition	Scope of Work
				• New insulated cold-room door with heater frame (0.8 x 1.8 m) • New pressure relief device (PRD)
12	Chiller	330 x 450 x 280	0 °C to 3 °C	• Dismantle and dispose existing units • New refrigeration system (medium-temp) • New control panel • New pressure relief device (PRD)
11	Chiller	420 x 430 x 280	0 °C to 3 °C	• Dismantle and dispose existing units • New refrigeration system (medium-temp) • New control panel • New pressure relief device (PRD)
21	Chiller	430 x 430 x 280	0 °C to 3 °C	• Dismantle and dispose existing units • New refrigeration system (medium-temp) • New control panel • New pressure relief device (PRD)

GENERAL SCOPE OF WORK

- Dismantling of the existing indoor and outdoor refrigeration units in all five (5) rooms and removal from site.
- Supply, installation, testing and commissioning of new refrigeration systems (indoor evaporators and outdoor condensing units) with all associated accessories. **Condensing Units Brand: DORIN ITALY or EMERSON COPELAND with matching evaporators THERMOWAY OR ICEMAKE. CU with Semi-hermetic compressors.**
- Supply and installation of refrigerant piping, insulation, fittings and accessories between indoor and outdoor units.
- Supply and installation of new control panels for each room, including temperature controllers and defrost control where applicable.
- Supply and installation of new pressure relief devices (PRDs) for each cold room.

- Electrical termination from the existing isolators already available at site to the new equipment.
- Supply and installation of two (2) new insulated cold-room doors with integrated heater for the freezer rooms (Room 13 and converted Room 20). Single-leaf hinged type, clear opening 0.8 m × 1.8 m.
- Provision of a suitable mobile crane for lifting and positioning of outdoor condensing units.
- Full testing and commissioning, including pull-down test, leak test, and handover with commissioning report.

EXCLUSIONS

The following items are explicitly excluded from our lump-sum offer and, if required, shall be the responsibility of the Client:

- Any Qatar Steel / MIC site permits, security passes, gate passes, and associated fees.
- Work or supply items not clearly listed within the scope above.
- Civil, structural, or builder's works (core drilling, openings, plinths, etc.).
- Replacement of cold-room insulated panels, floors, or ceilings.
- Modification or replacement of existing power isolators, cabling upstream of the isolators, or main distribution boards.
- Any works required outside normal working hours on a premium basis.

COMMERCIAL TERMS

Lump Sum Price	QAR 175,000.00 (Qatari Riyals One Hundred Seventy-Five Thousand Only)
Price Basis	Lump sum, all-inclusive of supply, installation, testing and commissioning as per scope above.
Payment Terms	70 % advance payment on order confirmation. 30 % on completion and handover.
Delivery & Stock	Units are ex-stock as of the date of this offer (subject to prior sale). Installation can commence immediately upon receipt of advance payment.
Completion Period	Fifteen (15) calendar days from site mobilization.
Warranty	Twelve (12) months on manufacturing defects from date of commissioning, under normal operating conditions.
Validity of Offer	Seven (3) days from date of issue, subject to stock availability.
Currency & Taxes	All prices in Qatari Riyals (QAR), exclusive of any applicable government taxes or duties if imposed.

IMPORTANT NOTE ON STOCK AVAILABILITY

Units are currently ex-stock and we strongly advise prompt action to secure availability. Stock levels are low; should the units be committed elsewhere, the lead time for a fresh factory order is a minimum of **two to three (2-3) months**. Early confirmation will ensure that installation commences within the fifteen (15) day window committed above.

We trust the above is in line with your requirement and look forward to your valued order. Should you require any clarification, technical adjustment, or a site meeting to finalize the scope, we remain at your disposal.

Yours faithfully,

Metri Engineering Services W.L.L.

Eng. Fayez Metri 55572793

