TECHNICAL & COMMERCIAL PROPOSAL

To	**M/s Al Shams Trading & Contracting Co.**	**Our Ref.**	MES/QTN/2026/KNK-B01
Attn.	Projects / Procurement Department	**Date**	30 September 2026
Project	**Building (B+G+3+P.H) at Al Messila**	**Owner**	**Khalaf Nasser H Al-Kaabi**
Basis	ACMV Equipment Schedule ACMV-12, Rev. 02	**PIN No.**	36070019

Subject: Supply & Installation of Split Type AC Units, Staircase Pressurization Fan and Extract Air Fans

Dear Sir,

With reference to your enquiry and the approved ACMV equipment schedule for the above project, we are pleased to submit our proposal for the supply, installation, testing and commissioning of the split type AC units and ventilation fans, as detailed below.

1. SCOPE OF WORK

- Supply of 89 nos. decorative wall-mounted split AC units (69 × 2.0 TR and 20 × 1.5 TR) as per schedule ACMV-12, complete with indoor and outdoor units.
- Installation of indoor and outdoor units, including refrigerant copper piping with insulation, interconnecting cable between indoor and outdoor units, pressure testing, vacuuming, testing and commissioning.
- Supply and installation of 1 no. staircase pressurization fan (SPF-01) serving the staircase from Basement to Penthouse, including mounting and duct work, control panel, testing and commissioning.
- Supply and installation of 70 nos. wall-mounted extract air fans for toilets, baths and kitchens (Ground to Penthouse), including fixing, testing and commissioning.
- Floor-wise equipment quantities are given in the Annex.

2. PRICE SCHEDULE

Item	Description	Unit	Qty	Unit Rate (QAR)	Amount (QAR)
A	**SPLIT TYPE AIR CONDITIONING UNITS**				
A.1	Decorative wall-mounted split AC, 2.0 TR (inverter), 240V/1Ph/50Hz — FREGO	Set	69	2,800.00	193,200.00
A.2	Decorative wall-mounted split AC, 1.5 TR (inverter), 240V/1Ph/50Hz — FREGO	Set	20	2,475.00	49,500.00
				Sub-Total A	**242,700.00**
B	**STAIRCASE PRESSURIZATION FAN**				
B.1	SPF-01 — Staircase pressurization fan, Elektrovent DUCT-ML 804/B HT, rated 300°C / 2 hrs, 415V/3Ph/50Hz (including duct and control panel)	No.	1	30,050.00	30,050.00
				Sub-Total B	**30,050.00**
C	**EXTRACT AIR FANS (TOILETS, BATHS & KITCHENS)**				
C.1	Wall-mounted extract fan, Vortice MF 100/4" — Toilets (50 CFM)	No.	17	330.00	5,610.00
C.2	Wall-mounted extract fan, Vortice MF 120/5" — Baths (100 CFM)	No.	36	360.00	12,960.00
C.3	Wall-mounted extract fan, Vortice A-E 254 M — Kitchens (150 CFM)	No.	17	1,050.00	17,850.00
				Sub-Total C	**36,420.00**
				TOTAL — SUPPLY & INSTALLATION (A + B + C)	**309,170.00**

Total Amount in Words: *Qatari Riyals Three Hundred Nine Thousand One Hundred Seventy Only.*

3. EQUIPMENT & WARRANTY

- **Split AC units:** FREGO (Made in China). Warranty 1 year on complete unit plus an additional 4 years on the compressor (5 years total on compressor).
- **Pressurization & extract fans:** Elektrovent / Vortice (Made in Italy). Warranty 1 year.
- Installation workmanship warranty: 1 year from the date of testing & commissioning.

4. EXCLUSIONS

- Any electrical works, including power supply, cabling, isolators, DBs and breakers.
- Final termination cabling from the isolator to any equipment.
- Any Drain network or drain points should be arranged by client near the required locations.
- Any civil works, including core cutting, openings, chasing, making good, painting and outdoor unit plinths/supports.
- Any BMS works or integration.
- Any fire alarm / fire system integration works (including SPF-01 interface with the fire alarm system).
- PVC sleeves and risers for the refrigerant copper pipes.
- Any item or work not specifically mentioned in this proposal.

5. COMMERCIAL TERMS

- **Delivery: Partial Ex-stock, balance within** 10 weeks from receipt of confirmed PO and advance payment.
- **Payment:** 50% advance with PO, 40% against delivery of materials to site, 10% upon testing & commissioning.
- **Validity:** 10 days from the date of this proposal.
- **Currency:** All prices are in Qatari Riyals (QAR).

We trust our proposal meets your requirements and remain at your disposal for any further clarification.

Yours faithfully,

METRI ENGINEERING SERVICES W.L.L.



ANNEX — FLOOR-WISE EQUIPMENT QUANTITIES

Equipment	Basement	Ground	First	Second	Third	Penthouse	Total
Split AC 2.0 TR	—	14	17	17	17	4	**69**
Split AC 1.5 TR	2	6	4	4	4	—	**20**
SPF-01 (B to PH)	1	—	—	—	—	—	**1**
MF 100/4" (Toilet)	—	4	4	4	4	1	**17**
MF 120/5" (Bath)	—	8	9	9	9	1	**36**
A-E 254 M (Kitchen)	—	4	4	4	4	1	**17**