TECHNICAL & COMMERCIAL PROPOSAL

QUARTERLY PREVENTIVE MAINTENANCE
WITH CORRECTIVE MAINTENANCE EMERGENCY RESPONSE
FOR AIR-COOLED CHILLERS

Our Reference:	MES/QTN/2026/556-R1
Your Reference:	PR-2828916162
Date:	12 April 2026 (Revision 1)
Client:	Acciona Facility Services (Ministry of Finance)
Attention:	Mr. Muhammad Musthafa / Mr. Midhun KK
Project:	Ministry of Finance Buildings

1. EQUIPMENT SUMMARY

Asset Tag	Equipment	Brand/Model	Capacity	Qty	Location
CHIL	Air-Cooled Chiller	SKM / Carrier	128 TR	9	All Buildings

2. SCOPE OF WORK

Metri Engineering Services shall provide Quarterly Preventive Maintenance with Corrective Maintenance Emergency Scope Response for nine (9) air-cooled chillers at Ministry of Finance buildings.

PART A: QUARTERLY PREVENTIVE MAINTENANCE

2.1 Compressor Section

- Check compressor operating current and voltage
- Check compressor oil level and condition
- Check compressor crankcase heater operation
- Inspect compressor mounting and vibration isolators
- Check and record suction and discharge pressures
- Check superheat and subcooling values
- Inspect electrical connections and tighten as necessary

2.2 Condenser Section

- Clean condenser coils with water jet and coil cleaner
- Check and clean condenser fan blades

- Check condenser fan motor bearings and lubricate
- Check condenser fan motor current draw
- Inspect condenser coil fins for damage and straighten if required
- Check condenser airflow and clear any obstructions

2.3 Evaporator Section

- Check evaporator entering and leaving water temperatures
- Check chilled water flow rate and pressure drop
- Inspect evaporator for signs of leakage or corrosion
- Check insulation condition

2.4 Electrical & Controls

- Check and verify all safety controls operation
- Check high/low pressure cutouts
- Check oil pressure differential switch
- Check phase monitor/protector
- Inspect contactors, relays, and control wiring
- Check and review fault history logs
- Check control panel for proper operation of display and indicators

2.5 General

- Check refrigerant charge and compressor oil level
- Check all piping connections for leaks
- Check vibration isolators and flexible connections
- Verify proper unit operation through complete start-up cycle
- Prepare and submit service report after each visit

PART B: CORRECTIVE MAINTENANCE EMERGENCY RESPONSE

MES shall respond to emergency breakdown calls and provide corrective maintenance. All spare parts and materials shall be supplied by Acciona.

3. EMERGENCY RESPONSE COMMITMENT

Response Time (Working Hours)	Within 4 hours of call notification
Response Time (After Hours/Weekends)	Within 8 hours of call notification
Working Hours	Saturday to Thursday, 7:00 AM to 5:00 PM
Emergency Hotline	+974 44459207

4. SERVICE FREQUENCY

Contract Duration	3 Years
Maintenance Type	Non-Comprehensive (PM + CM Emergency Scope)
Scheduled PM Visits Per Year	4 Quarterly Visits
Total Scheduled PM Visits (3 Years)	12 Visits
CM Emergency Call-Outs	(as required)

5. INCLUSIONS

- All labor costs for quarterly preventive maintenance visits
- All labor costs for corrective maintenance emergency scope call-outs
- Tools, equipment, and testing instruments
- Condenser coil cleaning chemicals
- Refrigerant leak detection equipment and nitrogen for pressure testing
- Brazing equipment and consumables for repairs
- Recovery unit, vacuum pump, and charging equipment
- Detailed service reports after each PM visit and CM call-out
- 24/7 emergency call-out response
- Technical recommendations for repairs and improvements
- Coordination with client for scheduled visits and emergency response

6. EXCLUSIONS

- All spare parts and replacement components (to be supplied by Acciona)
- Refrigerant (to be supplied by Acciona)
- Compressor oil (to be supplied by Acciona)
- Filter driers, TXVs, solenoid valves, sensors (to be supplied by Acciona)
- Electrical components: contactors, capacitors, PCBs, relays (to be supplied by Acciona)
- Fan motors, fan blades, bearings (to be supplied by Acciona)
- Oil analysis (yearly)
- Condenser/evaporator coil replacements
- Chemical treatment for chilled water system
- Civil, structural, or access-related works
- Repairs due to negligence, misuse, or third-party damage
- Any rewinding or overhauling.
- Any works not explicitly mentioned in this proposal

7. COMMERCIAL OFFER

All prices are in Qatari Riyals (QAR) and exclusive of VAT.

Description	Qty	PM Visits	Price/Year
Quarterly Preventive Maintenance for Air-Cooled Chillers (128 TR each, SKM/Carrier)	9	4/Year	**140,000**
Emergency Corrective Maintenance Response	9	As Req.	

Year 1 Total (PM + Emergency CM)	**QAR 140,000**
Year 2 Total (PM + Emergency CM)	**QAR 140,000**
Year 3 Total (PM + Emergency CM)	**QAR 140,000**
GRAND TOTAL (3 YEARS)	**QAR 420,000**

Note: All spare parts, refrigerant, compressor oil, and replacement components shall be supplied by Acciona. MES provides labor only for emergency corrective maintenance activities.

8. PAYMENT TERMS

- Invoicing: Quarterly in advance or upon completion of each quarterly visit
- Payment: Within 30 days from invoice date
- Currency: Qatari Riyals (QAR)
- Mode of Payment: Bank transfer or cheque

9. VALIDITY

This proposal is valid for thirty (30) days from the date of submission.

10. TERMS & CONDITIONS

1. Access to all chiller units must be provided during scheduled maintenance visits and emergency call-outs.
2. Client shall ensure safe working conditions and power isolation when required.
3. Maintenance schedule to be mutually agreed upon contract award.
4. All spare parts and materials for corrective maintenance shall be supplied by Acciona.
5. MES shall notify Acciona of required spare parts immediately upon diagnosis.
6. Response time for emergency calls is subject to receipt of clear fault notification.
7. Any additional works beyond this scope will be quoted and approved prior to execution.
8. MES shall not be liable for pre-existing defects or conditions.

9. MES shall not be liable for delays caused by unavailability of spare parts from Acciona.
10. This contract may be renewed annually upon mutual agreement.
11. Either party may terminate with 30 days written notice.

We trust our proposal meets your requirements and look forward to being of service.

For any clarifications, please contact:

Metri Engineering Services W.L.L
+974 4445 9207 / 5557 2793
mes@mes.qa
www.mes.qa

متري للخدمات الهندسية ذ.م.م
ص.ب : ١٩٩٦٢ ,الدوحة - قطر
تليفكس: ٤٤١٢٧٦٧
P.O. Box 19962, Doha-Qatar
TelFax: 4412767
METRI ENGINEERING SERVICES W.L.L