



Date: April 15, 2026

Ref: MES/QTN/ABC-2026/04-18

M/s. Azure Beach Club
Kind Attn: Ms. Hanane
Mob: +974 7081 9283
Email: hanane.oubaha@accor.com

Subject: Ventilation System Maintenance, Compliance & Air Balance Inspection Reports

Dear Sir,

We thank you for the opportunity to submit our technical and commercial proposal for the above-referenced scope of works at **Azure Beach Club, Lusail**, in line with the Qatar Civil Defence Department (QCDD) Application Renewal requirements.

Metri Engineering Services W.L.L. (MES), is a specialist HVAC, and refrigeration services company with extensive experience in ventilation system inspection, Testing Adjusting & Balancing (TAB), and QCDD compliance reporting across commercial, hospitality, and mixed-use facilities in Qatar.

We have carefully reviewed your Request for Proposal and the associated HVAC drawings for the project. Our proposal addresses all three scope categories as specified in your RFP and is structured accordingly.

1. Scope of Work

The scope of work is divided into three categories as defined in the client's RFP, covering all Air Conditioning & Mechanical Ventilation (ACMV) systems installed at the Azure Beach Club facility.

1.1 Ventilation System Inspection & Maintenance Report

MES shall carry out a comprehensive inspection and assessment of all ACMV equipment and associated systems, including but not limited to:

A. Detailed Inspection and Assessment of:

- Air Handling Units (AHU), Fresh Air Handling Units (FAHU), and Fan Coil Units (FCU)
- Fresh air and exhaust ventilation systems
- Toilet, kitchen, and general exhaust fans
- Ductwork condition (leakage, insulation, and accessibility)
- Air filters condition and replacement status
- Fan motors, belts, and associated components

B. Inspection and Verification of:

- Fire dampers and motorized dampers
- Access panels and system accessibility

C. Additional Deliverables:

- Evaluation of overall system condition, performance, and operational efficiency
- Submission of a detailed maintenance report in line with QCDD requirements, including observations and recommendations



Applicable Equipment Summary (per project HVAC drawings):

Equipment Type	Quantity
Air Handling Units (AHU)	9
Fresh Air Handling Units (FAHU)	2
Make-up Air Handling Units (MAHU)	2
Fan Coil Units (FCU)	11
Heat Recovery Ventilators (HRV)	7
Toilet Extract Fans (TEF)	11
Extract Fans (EF)	8
Supply Fans (SF)	5
Kitchen Extract Units (KEU) & Kitchen Extract Fans (KEF)	4
Gas Purging Fans (GPF)	7
Bathroom Extract Fan (BEF)	1
Close Control Unit (CRAC)	1
Smoke Extract Fans (SEF)	2
Electrostatic Precipitator (ESP)	2

1.2 Compliance Report (QCDD Requirements)

MES shall prepare and issue an official compliance report suitable for Civil Defence submission, covering the following:

A. Verification of ACMV System Compliance with:

- Qatar Civil Defence (QCDD) regulations
- Applicable international standards (ASHRAE, SMACNA, etc.)

B. Testing and Verification of Life Safety Integration, Including:

- Smoke extraction systems
- Staircase and corridor pressurization systems

C. Life Safety Equipment Covered Under QCDD Ventilation Test:

SL	System / Equipment	Quantity
01	Staircase Pressurization System – Differential Pressure & Performance Verification Test	02 Staircases / 04 Fans
02	Lift shaft Pressurization Fans – Performance Verification Test	02 Fans
03	Smoke Extract & Fresh Air Fan Performance Verification Test (Generator Room / MEP Basement)	03 Fans
04	Submission of Final Reports in QCDD New Formats	All Above

Note: QCDD smoke management / ventilation test reports shall be issued by our approved certified engineer, through our specialist subcontractor, in compliance with QCDD requirements. MES shall coordinate the full process including site testing, report preparation, and QCDD inspection attendance.



1.3 Air Balance Inspection, Testing & TAB Report

MES shall carry out full Testing, Adjusting, and Balancing (TAB) of the complete ventilation system in accordance with ASHRAE / SMACNA standards, including:

A. Measurement and Recording of:

- Supply, return, and exhaust airflow rates for all AHUs, FAHUs, MAHUs, HRVs, and extract/supply fans
- System performance parameters (fan speed, motor current, static pressure, temperature differentials)

B. Verification of Room Pressurization:

- Negative pressure verification (toilets, service areas, kitchens)
- Positive pressure verification (corridors, escape routes, lobbies)

C. Submission of:

- Pre- and post-balancing readings
- Instrument calibration certificates
- Completion of the Air Balance Inspection & Testing Report

2. Deliverables

- Hard Copy: Minimum 3 sets of each report
- Soft Copy: PDF format

Reports shall include:

- Detailed test results and readings
- System assessment and observations
- Recommendations (if any)



3. Commercial Offer

The pricing for the subject scope of works is detailed below per RFP category:

SL	Description	Amount (QAR)
1.1	Ventilation System Inspection & Maintenance Report – Comprehensive inspection and assessment of all ACMV equipment (AHUs, FAHUs, FCUs, MAHUs, HRVs, extract/supply fans, ductwork, dampers, filters, motors & belts) including detailed maintenance report with observations and recommendations per QCDD requirements.	35,500
1.2	Compliance Report (QCDD Requirements) – ACMV system compliance verification against QCDD regulations and international standards; life safety integration testing including staircase & lift shaft pressurization, smoke extract, issuance of report with certified engineer stamp; QCDD inspection attendance (one time).	29,000
1.3	Air Balance Inspection, Testing & TAB Report – Full Testing, Adjusting and Balancing of all ventilation systems per ASHRAE/SMACNA standards; measurement of supply, return, and exhaust airflow rates; room pressurization verification; pre/post balancing readings; instrument calibration certificates; completion of Air Balance Inspection & Testing Report.	57,500
	Subtotal	122,000
	VAT (if applicable) – excluded	–
	TOTAL (Excl. VAT)	QAR 122,000

Pricing Notes:

- All prices are in Qatari Riyals (QAR) and exclusive of VAT.
- Scope 1.2 includes QCDD-certified ventilation system testing, report issuance, and one-time QCDD inspection attendance.
- Any additional QCDD re-inspection visits beyond the first shall be quoted separately as a variation.
- Pricing is based on the equipment quantities derived from the project HVAC drawings provided. Any increase in equipment quantities or additional systems shall constitute a variation.

4. Payment Terms

- 50% advance payment upon acceptance of this proposal and issuance of work order.
- 50% upon submission of all final reports.
- Payment shall be due within 15 days from the date of invoice.

5 Items to be Provided by the Client / Facility Management

- Unrestricted access to all mechanical rooms, risers, plant rooms, rooftop equipment, and ceiling voids throughout the duration of works.
- Ladders, scaffolding, and man-lifts as required for access to high-level equipment.
- Sufficient number of helpers (minimum one helper per working MES team) for ceiling tile removal, access panel opening, etc.
- Hard copy A1-size as-built HVAC drawings and equipment submittals.

- Power supply for testing instruments.
- False ceiling technicians to remove and reinstate tiles wherever needed.
- Drilling of required probe holes for static pressure and traverse readings (if applicable).
- Coordination with fire alarm contractor for FAS interlocking and damper testing.
- All systems operational and in running condition prior to commencement of testing.

6. Exclusions & Remarks

- Anything not explicitly mentioned in this proposal is excluded from the scope.
- Any civil, electrical, plumbing, or fire alarm related works at site.
- Supply of spare parts, replacement filters, belts, or any consumables.
- Repair, modification, or rectification works of any kind.
- Supply and installation of dampers, valves, gauge cocks, or any missing accessories.
- BMS/PLC programming or integration.
- Supply and installation of transformers or generators.
- Re-inspection by QCDD beyond the first attendance is not included and shall be a variation.

7. Mobilization & Duration

- Mobilization: Within 10 working days from receipt of work order and advance payment.
- Estimated duration of works: 15–20 working days (subject to site access and system readiness).
- Report submission: Within 10 working days from completion of site works.
- Working hours: 7:00 AM to 5:00 PM, Saturday to Thursday (or as coordinated with the facility).

8. Validity

This offer is valid for a period of **15 days** from the date of this proposal. MES reserves the right to revise the offer after the validity period.

We trust our proposal meets your technical and commercial requirements. We remain at your disposal for any clarifications and look forward to your favorable response.

Yours faithfully,

For Metri Engineering Services W.L.L.



Eng. Fayez Metri

Managing Director

Tel: +974 4445 9207 | Mob: +974 7050 0311