



TECHNICAL QUOTATION

Louvers & Fresh Air Assessment for AHUs — Dukhan Hospital

Date: 09 May 2026

Validity: 30 Days

Ref: MES/QTN/DH-2026/493

Subject: Technical Assessment of Louvers & Fresh Air Supply for Air Handling Units (AHUs)

1. Introduction

Metri Engineering Services W.L.L. (MES) is pleased to submit this quotation for the technical assessment of louvers and fresh air supply serving the Air Handling Units (AHUs) and Package Air Conditioning units at Dukhan Hospital.

2. Scope of Work

The scope of this assessment include the following:

1. Measuring the existing air flow for 39 nos openings connected to the related AHU(s) or Package AC units.
2. Measuring the pressure of the fresh air duct
3. Preparing a schedule of all measurements and collected data.
4. Recording all technical remarks, observations, and field notes for reporting.
5. Measuring the fresh air flow on each AHU or Package AC unit.
6. Upon completion of the assessment and technical report, MES shall provide a technical proposal for the selection of sand trap louver dimensions and the required air balancing to maintain the initial fresh air flow rate and room static pressure.

3. Deliverables

Upon completion of the field assessment, MES shall deliver:

- Comprehensive measurement data schedule (air flow rates & static pressures).
- Technical assessment report with field observations and remarks.
- Technical proposal for sand trap louver selection (dimensions and specifications).
- Air balancing recommendations to preserve initial fresh air flow and room pressures.

4. Commercial Summary

Description	Details
Project	Dukhan Hospital – Louvers & Fresh Air Assessment for AHUs
Scope	Site measurements, technical assessment report, sand trap louver proposal & air balancing recommendations
Lump Sum Price	QAR 15,000



NET PRICE AFTER SPECIAL DISCOUNT = QAR 14,000

Validity

30 calendar days from the date of this quotation

4. 5. Payment Terms

Milestone	Percentage	Amount (QAR)
Advance payment upon order confirmation	50%	7,000.00
Upon completion and report submission	50%	7,000.00
Total Contract Value		14,000

5. 6. General Notes & Exclusions

- All prices are in Qatari Riyals (QAR) and exclude VAT (if applicable).
- Access to all AHU rooms, louver locations, and served areas shall be provided by the client.
- Any civil, structural, or scaffolding works required for access are excluded from this quotation.
- Supply and installation of sand trap louvers is not included; these will be covered under a separate technical and commercial proposal following the assessment.
- Working hours shall be coordinated with hospital management to minimize disruption to operations.

Metri Engineering Services W.L.L

Eng. Fayeze (55572793)

