QUOTATION

To	**M/s Alfaisal Holding**
Attention	Eng. Kamel
Ref.	MES/QTN/2026/370
Date	31 October 2026
Project	**Relocation of Refrigeration Equipment – Al Samerya Poultry Farm to Al Shananiya Farm**
Subject	**Dismantling, shifting, re-installation, testing and commissioning of existing refrigeration units**

Dear Eng. Kamel,

With reference to your request, we are pleased to submit our offer for relocating the existing refrigeration equipment from Al Samerya Poultry Farm and re-installing it at Al Shananiya Farm. Our scope, exclusions and commercial terms are detailed below.

1. Scope of Work

1. **Dismantling at Al Samerya Poultry Farm**
   - Joint pre-dismantling inspection with the client, and tagging of all equipment. Preparation of shop drawings based on the new location and the existing equipment to be used.
   - Dismantling of the existing refrigeration units only: condensing units, evaporators, refrigerant piping and controllers.
   - Loading and shifting of the dismantled equipment to Al Shananiya Farm.
2. **Re-installation at Al Shananiya Farm**
   - Positioning and fixing of the condensing units and evaporators at the dedicated locations.
   - Re-installation of the refrigerant piping between condensing units and evaporators.
   - Re-installation and connection of the controllers.
3. **Testing and Commissioning**
   - Pressure testing with nitrogen, leak testing and vacuuming of the refrigerant circuits.
   - Refrigerant charging, start-up, and setting of controller parameters.
   - Pull-down test of each room, and handover to the client.

2. Exclusions and Clarifications

1. **Condition of existing equipment:** MES is not responsible for the condition of the existing equipment. Any part or equipment found to need repair or replacement after re-installation and testing will be quoted separately.
2. **Refrigeration equipment only:** Our scope covers the refrigeration equipment only. Dismantling, shifting and re-erection of sandwich panels, cold room doors and floor insulation are excluded.
3. **Additional materials:** Any materials needed for re-installation at the new site such as extra copper pipes, pipe insulation, power cables, control cables and refrigerant will be identified and notified to the client. The client may arrange these directly, or MES can quote them separately.

1. **Power supply:** Power to the indoor and outdoor refrigeration units at their dedicated locations is to be provided by the client's electrical subcontractor.
2. **Site readiness:** Re-installation will start once the cold rooms at Al Shananiya Farm are erected and the unit locations are ready and accessible.

3. Commercial Offer

Description	Amount (QAR)
Dismantling, shifting, re-installation, testing and commissioning of the existing refrigeration equipment, as per the scope above (lump sum)	330,000
Total Lump Sum	**330,000**

Amount in words: Three Hundred Thirty Thousand Qatari Riyals Only.

Payment Terms

Milestone	Share	Amount (QAR)
Advance payment with order	30%	99,000
Against dismantling and shifting to new site and drawings preparation	20%	66,000
Against Completion of installation	30%	99,000
Against testing and commissioning	20%	66,000
Total	**100%**	**330,000**

4. General Terms

- **Validity:** 30 days from the date of this quotation.
- **Completion period:** To be agreed upon order, subject to site readiness at Al Shananiya Farm.
- **Warranty: 1 year Installation** Workmanship on the relocation works only; no warranty is given on the existing equipment.

We trust our offer meets your requirements and remain at your disposal for any clarification.

Yours faithfully,

METRI ENGINEERING SERVICES W.L.L.
Eng Fayez (55572793)

