

TECHNICAL & COMMERCIAL PROPOSAL

Replacement of Package Unit AC Ductwork – Sheikh Turki Palace

To:	Al Jazi Real Estate Properties	Date:	15 April 2026
Attn:	Hope Virgil Getizo – Procurement Engineer	Ref:	MES/QTN/2026/0309-OPR-26-rev1
Project:	Replacement of AC Duct at Sheikh Turki Palace – Ref: 0309/OPR-26		
Location:	Sheikh Turki Palace, Doha, State of Qatar		

Dear Ms. Hope Virgil Getizo,

We refer to your Request for Quotation dated 01 April 2026 (Ref: 0309/OPR-26) for the Replacement of AC Duct at Sheikh Turki Palace, Doha. We are pleased to submit our Technical and Commercial Proposal for your consideration.

1. Scope of Works

The following scope of works is included in this proposal, as per the issued Scope of Work document:

1.1 Dismantling and Disposal of Existing Ductwork

- Careful dismantling of existing damaged / deteriorated ductwork
- Isolation of duct sections to avoid disturbance to operational systems
- Protection of surrounding equipment, ceilings, and services during dismantling
- Removal of all associated components – supports, hangers, and existing insulation
- Safe handling, transportation, and disposal of dismantled materials in accordance with site and environmental regulations
- Cleaning of work area prior to new duct installation

1.2 GI Duct Fabrication and Installation

- Fabrication, supply, and installation of GI ducts (0.8 mm / 22-Gauge sheet thickness)
- Duct fabrication in compliance with SMACNA standards
- Installation inclusive of all accessories: flanges, cleats, stiffeners, gaskets, silicone sealant, nuts and bolts, hangers, and supports
- Proper alignment, leveling, and airtight jointing throughout

1.3 Duct Insulation Works

- Supply and installation of 50 mm thick fiberglass insulation
- Fixed using approved adhesive method with proper joint sealing and taping
- Application of canvas cloth covering over insulation
- Application of vapor barrier coating to prevent condensation

1.4 Aluminum Cladding Works

- Supply and installation of 0.7 mm thick aluminum cladding for all exposed roof ducts
- Proper overlapping, sealing, and weatherproofing of cladding joints
- Cladding secured with appropriate fasteners and supports

1.5 Testing, Inspection and Handover

- Inspection of duct alignment and installation quality
- Checking for air leakage and verification of proper sealing
- Verification of insulation and cladding integrity

1.6 Waterproofing at Duct Penetration Areas

- Supply and installation of waterproofing membrane at all duct penetration openings through roof
- Proper sealing and waterproofing treatment around each package unit duct shaft penetration
- Applicable to all 8 package units

1.7 Sound Attenuator Removal and Reinstallation

- Careful removal of existing sound attenuators from the ductwork prior to dismantling
- Reinstallation and reconnection of attenuators into new ductwork upon completion
- Applicable to all 8 sound attenuators (1 per package unit)

Inclusion Note: Waterproofing at duct penetration areas and sound attenuator removal/reinstallation are now included in this revised proposal.

3. Bill of Quantities (BOQ)

Quantities are as per the BOQ issued by Al Jazi Real Estate Properties.

No.	Description	UOM	Qty (LM)	Duct Area (m ²)	Lump Sum Price (QAR)
1	Package Unit 8 – GI Duct (100 × 32 cm)	LM	15.8	41.712	136,845 Q.R.
2	Package Unit 9 – GI Duct (66 × 36 cm)	LM	19.2	39.168	
3	Package Unit 6 – GI Duct (76 × 42 cm)	LM	14.0	33.04	
4	Package Unit 7 – GI Duct (95 × 36 cm)	LM	14.0	37.38	
5	Package Unit 5 – GI Duct (140 × 42 cm)	LM	19.0	72.072	
6	Package Unit 3 – GI Duct (100 × 40 cm)	LM	13.8	38.64	
7	Package Unit 2 – GI Duct (66 × 40 cm)	LM	16.0	33.92	
8	Package Unit 1 – GI Duct (110 × 50 cm)	LM	14.7	47.04	

No.	Description	UOM	Qty (LM)	Duct Area (m ²)	Lump Sum Price (QAR)
9	Waterproofing with membrane at duct penetration areas	No.	8	–	8,000 Q.R.
10	Removal and reinstallation of existing sound attenuators	No.	8	–	2,400 Q.R.
TOTAL			126.5	342.972	147,245 Q.R.

*Above pricing based on the QTY provided. If any extra QTY found at site, it will be charged separately.

3. Commercial Terms & Conditions

Total Price	147,245 Q.R.
Payment Terms	50% advance upon issuance of LPO; 50% upon completion and client acceptance
Validity	This quotation is valid for 3 days from the date of submission
Warranty	12 months from date of handover, covering fabrication, installation, insulation, and cladding performance
Execution Timeline	Works to be completed within 15-20 days from receipt of LPO and advance payment.
Standards	SMACNA / approved HVAC standards and project specifications
Exclusions	Any works not explicitly listed in the attached BOQ.

We trust this proposal meets your requirements and look forward to your favorable response.

METRI ENGINEERING SERVICES W.L.L

