

M/s Lusail International Circuit Kind Attn: Mr. Amr Hussain E-Mail: amr.hussain@lscs.qa Mobile: +97477988486	QREF 17/06/2026-11 Subject: Installation, Testing & Commissioning of 2 nos. Package AC Units for Workshop 01 Area 02 with duct works, civil and electrical works. Location : Workshop 01 Area 02
DATE : 17/06/2026	Email: mes@mes.qa

Dear Sir,

With reference to your inquiry concerning Supply, Installation, Testing & Commissioning of Additional Package AC Units for Workshop 01 Area 02 Warehouse at LIC, we would like to submit our proposal, which took into consideration all your requirements for this project's scope of works.

Scope of works:

1. Installation, testing and commissioning of 2 nos. PACKAGED air conditioning (Brand: MIDEA MODEL# MRCT-300CWN1-R(C) PROVIDED by client 30 TR EACH) which is sufficient to AREA 02



2. Supply & Installation 2 nos. Textile Duct lines along the whole warehouse (AS PER ATTACHED SKETCH) for proper air distribution inside the warehouse. Supply & Installation of Outside duct will be GI Duct insulated by THERMOBREAK duct insulation.



3. Provide 2 nos concrete plinth to place the package ACs.
4. All wall holes to be properly fixed and sealed.
5. Electrical works related (from existing DB @ Electrical Room till package ACs, Cabling, Isolators. Provide the necessary modification of the existing panel and outgoing MCCBs to feed the package ACs Necessary Cables, Cable trays/trunks Weatherproof Isolators.
6. Provide necessary Scaffolds for installation.
7. Supply & Installation of Motorized Fire Dampers for Return Duct & Fusible Fire Dampers for Supply Duct.
8. Fire Interface modules for the Package ACs with the existing Fire Control Panel
9. Fire Interface modules for the Roof Fans with the existing Fire Control Panel
10. Testing & Commissioning of the above.

Excluding: Dismantling of racking system or shifting any stored materials inside/outside.

Warranty: 1 year full + 4 additional years for compressors only against manufacturing defects.



BOO

DESCRIPTION	QTY	Unit Price	Total Price
1) Installation of 2 nos. Existing PACKAGED air conditioning (Brand: provided by client 30TR each) including Thermostat and control wiring	2	10,000	20,000
2) Supply & Installation of Textile Circular Duct (Internal duct) as per duct layout for 2nos Package Acs to cover the area	2	27,500	55,000
3) Supply & Installation of GI duct (external duct) with THERMOBREAK Duct Insulation for exposed duct.	2	18,000	36,000
4) Construction of Foundation base for 2 nos package ACs	2	3,500	7,000
5) Electrical works related from Existing SMDB PANEL including modification @ Electrical Room which is suitable to take extra load till Package ACs including cables, Isolators, necessary Cable trays/trunks Weatherproof Isolators.	LS	157,000	157,000
6) Supply & Installation of Motorized Fire Dampers for Return Duct & Fusible Fire Damper for Supply Duct.	LS	36,000	36,000
7) Fire Interface modules for the Package ACs with the existing Fire Control Panel	LS	10,000	10,000
8) Fire Interface modules for the Roof Fans with the existing Fire Control Panel so the fans will work only by command from Fire Panel	LS	10,000	10,000
9) Testing & Commissioning	LS	10,000	10,000
Total PRICE Q.R.=			341,000

Delivery Time: 4 → 6 weeks from advanced payment date & PTW

Offer Validity: This proposal is valid for 10 days

Warranty: 400 days

Payment Terms: 50% Advance along with PO.
30% Upon Supply of Electrical Materials to site.
20% Against Installation, Testing & Commissioning

Assuring you our professional cooperation

METRI ENGINEERING SERVICES W.L.L

