



M/s HILTON DOHA Kind Attn: Eng. Aya Ataya – Project Engineer Cc: Mr. Harun Cengiz E-Mail: Aya.Ataya@hilton.com Mobile: +974 6655 9580	QREF 21/09/2026-1 Rev.1 Subject: Quotation for Air & CHW System Pre-Commissioning, Supervision of Rectification Works and TAB Works (Phased) Project Title: Hilton Doha
DATE: 22/09/2026	Email: mes@mes.qa

Dear Eng. Aya,

With reference to your request, we are pleased to submit our offer for the Air and Chilled Water (CHW) Systems at Hilton Doha, structured in three sequential phases:

- **Phase 1 – Pre-Commissioning / Initial Assessment:** meetings with the hotel maintenance team to identify the deficient areas, assessment of the main chilled water pump room, air and water measurements of the affected areas, and a recommendation report with the full rectification scope for Hilton to RFQ from contractors.
- **Phase 2 – Supervision of Rectification Works:** supervision of the rectification contractor appointed by Hilton, through to close-out of the deficiencies identified in Phase 1.
- **Phase 3 – Testing, Adjusting & Balancing (TAB):** air and water balancing of the rectified systems.

Price Summary

Phase	Description	Lump Sum (QAR)
Phase 1	Pre-Commissioning / Initial Assessment of affected areas: maintenance team meetings, main CHW pump room assessment, air & water measurements of affected areas, and recommendation report with full rectification scope	52,500.00
Phase 2	Supervision of rectification / repair / modification works carried out by the rectification contractor appointed by Hilton	30,000.00
Phase 3	Testing, Adjusting & Balancing (TAB) – Air & Water Balancing	90,600.00
	Total – Phases 1, 2 & 3 (Qatari Riyals)	173,100.00

PHASE 1 – PRE-COMMISSIONING / INITIAL ASSESSMENT

Phase 1 addresses the zones / areas where performance issues are reported by the hotel, in order to define the rectification works required before TAB.

1.1 Meetings with Hilton Maintenance Team

- Conduct meetings with the maintenance supervisor / team to highlight the list of deficient areas / zones.
- Establish the history of each area / zone, whether it is a cooling issue, airflow issue, humidity issue or defective equipment.

1.2 Main Chilled Water Pump Room Assessment

- Assess the main chilled water pump room and verify that the running pumps are delivering the required water flow and water temperatures, before proceeding to the affected zone / area branches.

1.3 Assessment of Affected Areas

- After highlighting the weak points / affected areas with the hotel maintenance team, take air and water measurements for the equipment serving the affected areas, and assess the condition of the related equipment.
- Identify the rectification / repair / replacement / upgrade required for each highlighted zone / area, whether it is a cooling, airflow or humidity issue.

1.4 Areas without Complaints

- Areas where there is no complaint shall be visited during the full TAB works under Phase 3.

1.5 Recommendation Report & Rectification Scope

- Generate the recommendation report for the affected zones / areas, with the measurements taken and the findings.
- Define the full scope required, whether repair, replacement, modification or upgrade, with full details, for Hilton to issue an RFQ to contractors.

The report shall be submitted in soft copy (PDF and editable format). Any rectification, repair, replacement or modification works shall be quoted separately upon request.

1.6 Testing Instruments

All measuring techniques and instrumentation are in accordance with NEBB standards, and all instruments carry valid calibration certificates:

- Digital manometer / differential pressure gauges; Pitot tube; rotating-vane and anemometers; air flow capture hood.
- Digital flow meter for DRVs, PICVs
- Digital tachometer



1.7 Duration & Proposed Schedule

Activity	Duration Phase 1
Meetings with Hilton maintenance supervisor / team; list of deficient areas / zones and their history	6 weeks
Main chilled water pump room assessment	
Air and water measurements and equipment condition assessment of the affected areas	
Recommendation report and full rectification scope – draft submission	
Issue of final report	

The programme is based on access being granted to guest rooms, plant rooms, service and back-of-house areas in accordance with an access schedule agreed with Hilton Doha.

1.8 Phase 1 Exclusions

- Ceiling openings & access where required for hidden test points to be provided by client.
- Any gypsum work like opening and closing and access panels.
- Any kind of duct modification or accessories to the existing duct. Any required repair to the existing units or ducts is excluded and the above price doesn't include re-current visits and re-measurement.
- Any leak rectification for ducts.
- Equipment startup and initial commissioning by equipment supplier.
- DRVs or PICVs where not available & test plugs.
- Ceiling openings where required for hidden DRVs to be provided by client.
- Startup, testing & commissioning of chillers, pumps, AHUs, FCUs by client.
- Any kind of water flushing and chemical treatment.
- Any leak rectification from chilled water pipes.
- Strainers cleaning; filters cleaning should be done by client team before we start the work.
- Lifting equipment where needed to perform the measurement and adjustment.
- Anything not mentioned in the above scope.

1.9 Phase 1 Price & Payment Terms

Lump sum price for Phase 1 – Pre-Commissioning / Initial Assessment = 52,500 Q.R.

- 50% advance along with order; 50% against final report submission.



PHASE 2 – SUPERVISION OF RECTIFICATION WORKS

Following Phase 1, Hilton will appoint a rectification contractor, either us or others at a separate cost, to carry out the rectifications, repairs and modifications identified in the Pre-Commissioning Report. MES shall supervise these works on Hilton's behalf as follows:

2.1 Scope of Supervision

- Attend the kick-off meeting with Hilton and the rectification contractor, and brief the contractor on the deficiency / recommendation schedule and the works required prior to TAB.
- Review the contractor's method statements and proposed replacement materials / equipment for technical compliance with the Phase 1 recommendations.
- Site inspection of the rectification works.
- Raise observations / non-conformances to Hilton and the contractor where works do not meet the recommendations.
- Verify and witness functional re-checks of rectified items.

2.2 Phase 2 Price & Payment Terms

Lump sum price for Phase 2 – Supervision of Rectification Works = 30,000 Q.R.

- 50% advance along with order; 50% against Final Close-Out Report submission.

PHASE 3 – TESTING, ADJUSTING & BALANCING (TAB)

Phase 3 shall commence upon issue of the Phase 2 Final Close-Out Report confirming the systems are ready for TAB.

3.1 Equipment Covered

- 77 Nos. FAHU & AHU
- 526 Nos. FCU
- Air terminals related to the above.

3.2 Scope of Works

Air Balancing: This section covers the performance checks of equipment and air balancing. All measuring, balancing techniques and instrumentation utilized are in accordance with NEBB standards and all tools / instrumentation are with valid calibration certificates. All ducted systems will be measured and balanced by manometers, anemometer and air flow hood for balancing air terminals. All readings will be recorded and presented in a tabulated report.

Water Balancing: This section covers measurement for the chilled water network related to the air conditioning systems as detailed in the schedule of equipment. Measurements will be conducted using the current NEBB standards. All DRVs / PICVs will be measured using a digital flow meter with a valid calibration certificate. The operational checks of all pumps will include correct rotation, motor running speeds and total flow rates. All readings will be recorded and presented in a tabulated format.

3.3 Duration & Proposed Schedule: 8 Weeks

3.4 Phase 3 Exclusions

- Ceiling openings and access where required for hidden test points and hidden DRVs, to be provided by the client.
- Any gypsum work, including opening and closing and access panels.
- Any duct modification or accessories to the existing duct; any repair to the existing units or ducts.
- Re-current visits and re-measurement.
- Any leak rectification for ducts or chilled water pipes.
- Equipment startup, testing and initial commissioning of chillers, pumps, AHUs and FCUs by the equipment supplier.
- DRVs or PICVs where not available, and test plugs.
- Any water flushing and chemical treatment; strainer cleaning.
- Lifting equipment where needed to perform the measurement and adjustment.

3.4 Phase 3 Price & Payment Terms

Lump sum price for Phase 3 – Air & Water Balancing = 90,600 Q.R.

- 50% advance along with order; 50% against final report submission.

GENERAL EXCLUSIONS & COMMERCIAL TERMS

General Exclusions (all phases)

- Any rectification, repair, replacement or modification works; Phase 1 and Phase 3 cover assessment and TAB only, and Phase 2 covers supervision only.
- Any dismantling or intrusive inspection of equipment, ductwork, pipework or valves.
- Provision of drawings, equipment data sheets, system information and previous TAB reports, to be provided by the client.
- Arrangement of access to guest rooms, occupied areas, plant rooms and service areas, to be provided by the client.
- Any statutory approvals, permits or third-party certification.
- Anything not mentioned in the above scope.

Commercial Terms

- Prices are in Qatari Riyals, lump sum per phase, and are based on the quantities stated above. Variation in quantities exceeding $\pm 5\%$ shall be subject to price adjustment on a pro-rata basis.
- Each phase shall be confirmed by a separate order or by a single order covering all phases; the phases are carried out in sequence.
- Works shall be carried out during normal working hours unless otherwise agreed.
- Validity of Offer: 30 days from the date of this quotation.

We trust the above meets your requirements and remain at your disposal for any clarification.

METRI ENGINEERING SERVICES

Eng. Fayez (55572793 / 70500311)

