

M/s Schneider Electric Services LLC	QREF 08/06/2026-3
	Subject: Supply & installation of Duct Split AC units for Warehouse @ Busulba.
	Location : GWC Warehouse Busulba
DATE : 08/06/2026	Email: mes@mes.qa

Dear Sir,

With reference to your inquiry concerning Supply & installation of AC units for Warehouse @ Bu sulba, we would like to submit our proposal, which took into consideration all your requirements for this project's scope of works.

Scope of works:

1. Supply, Installation, testing and commissioning of **4 nos. DUCT SPLIT ACS COOLING CAPACITY 23.50kw/35°C PEV-P200YM/PUV-P200YMA (6 Ton Capacity each).** (Brand: **mitsubishi electric** R410A – INVERTER DUCTED TYPE)
2. Supply & Installation of **PIR Duct lines along the wall side** for proper air distribution inside the warehouse @ block wall level.
3. All holes to be properly fixed and sealed
4. Electrical works related (from existing DB, upgrade the existing outgoing 63amp MCCB to 80Amp) then provide new sub DB for the new ACs with related cables/isolators.
5. Provide necessary Lifting Equipment & Scaffolds for installation.
6. Testing & Commissioning of the above.



METRI ENGINEERING SERVICES W.L.L.
متري للخدمات الهندسية ذ.م.م

Excluding: Dismantling of racking system or shifting any stored materials.

Any approval from KAHRAMA or 3rd party consultant or QCDD.

Notes

- 1) Rack Dismantling if required or shifting any stored materials at site are client responsibility

Warranty: 1 year full + 4 years additional on the original fixed compressors.

TOTAL PRICE Q.R. = 166,500 Q.R.

Special Discount= - 20,000 Q.r.

Net Price= 146,500 Q.R.

Delivery Time: 4-6 weeks from advanced payment date & PTW

Offer Validity: This proposal is valid for 5 days

Payment Terms: 70% Advance along with contract signing
20% Upon Supply of ACs to site
10% Against Installation, Testing & Commissioning

Assuring you our professional cooperation

METRI ENGINEERING SERVICES W.L.L

