

TECHNICAL BID (UN-PRICED OFFER)

Tender No. PW/01-2/CP/TDR-18/2026

Our Offer Ref.: MES/QTN/2026/0416-01 Rev.1	Date: 13 July 2026	Offer Validity: 90 days from tender closing date
--	--------------------	--

To:

The Chief Materials & Shared Services Officer

Qatar Steel Company (Q.P.S.C.)

P.O. Box 50090, Mesaieed, State of Qatar

Subject: Technical Bid – Tender No. PW/01-2/CP/TDR-18/2026 — Supply, Installation & Commissioning of Refrigeration Units for Cold Stores in Qatar Steel's Kitchen Facility

Dear Sirs,

With reference to your Tender Invitation dated 30th June 2026, the Instructions to Bidders, Annexure-1 (Scope of Work), Annexure-2 (Priced Offer Format), the Draft Contract and the mandatory site visit held on 8th July 2026 at Qatar Steel's Kitchen Facility, we are pleased to submit our Technical (un-priced) Bid for the subject works.

Our offer covers the supply, installation, testing and commissioning of new refrigeration units for the five (5) cold store rooms of Qatar Steel's Kitchen Facility — three (3) chiller/cold store rooms (0 °C to +3 °C) and two (2) freezer rooms (–20 °C) — on a turnkey basis, in accordance with the tender scope of work and the specifications confirmed herein. Our Commercial (priced) Bid is submitted separately in accordance with the Instructions to Bidders.

We confirm our bid remains valid for ninety (90) days from the tender closing date, and we confirm our acceptance of Qatar Steel's right to place a partial order per Clause 9 of the Instructions to Bidders, with our quoted unit prices remaining firm for any such partial order.

Yours faithfully,

For Metri Engineering Services W.L.L.

Eng. Fayez Metri

Managing Director | Mob: +974 5557 2793 | mes@mes.qa





1. Bidder Information

Name of Bidder	Metri Engineering Services W.L.L. (MES)
Postal Address	P.O. Box 37383, Doha, State of Qatar
Telephone / E-mail	+974 5557 2793 / mes@mes.qa • www.mes.qa
Contact Person for Tender	Eng. Fayez Metri — Managing Director
Commercial Registration No.	[CR No. — 32209]

2. Project Understanding & Basis of Offer

This tender is issued for the replacement of the existing cold store refrigeration equipment in Qatar Steel's Kitchen Facility at Mesaieed Industrial City (MIC). Following our attendance at the mandatory site visit and our detailed site survey, our offer is based on the replacement of the refrigeration systems in five (5) rooms, achieving the tendered configuration of:

- **Three (3) chiller / cold store rooms** maintained at 0 °C to +3 °C — 3 refrigeration units;
- **Two (2) freezer rooms** maintained at –20 °C — 2 refrigeration units (including the conversion of one existing chiller room to freezer duty).

Room identification below follows the tender drawing 2596A-ACMV-B1-1-004 REV.Z (clouded area). Room capacities have been selected with reference to the existing equipment capacities as instructed in Annexure-1, verified against our own heat load assessment for the surveyed room dimensions and design conditions.

3. Room-wise Scope of Work

Note: Room numbers below correspond to the Room IDs in tender drawing 2596A-ACMV-B1-1-004 REV.Z.

Room ID	Application	Dimensions L × W × H (cm)	Design Room Temp.	Scope of Work
1	Chiller — converted to Freezer	260 × 330 × 280	–20 °C	Dismantle & dispose existing units; new low-temperature refrigeration system (indoor + outdoor) with R404A; new control panel; new insulated cold-room door with heater frame (0.8 × 1.8 m); new pressure relief device (PRD).
2	Freezer	260 × 330 × 280	–20 °C	Dismantle & dispose existing units; new low-temperature refrigeration system (indoor + outdoor) with R404A; new control panel; new insulated cold-room door with heater frame (0.8 × 1.8 m); new pressure relief device (PRD).
3	Chiller / Cold Store	330 × 450 × 280	0 °C to +3 °C	Dismantle & dispose existing units; new medium-temperature refrigeration system (indoor + outdoor) with R404A; new control panel; new pressure relief device (PRD).
4	Chiller / Cold Store	420 × 430 × 280	0 °C to +3 °C	Dismantle & dispose existing units; new medium-temperature refrigeration system (indoor + outdoor) with R404A; new control panel; new pressure relief device (PRD).



5	Chiller / Cold Store	430 × 430 × 280	0 °C to +3 °C	Dismantle & dispose existing units; new medium-temperature refrigeration system (indoor + outdoor) with R404A; new control panel; new pressure relief device (PRD).
---	----------------------	-----------------	---------------	---

4. Technical Specification & Compliance with Annexure-1

Tender Requirement (Annexure-1)	MES Offer / Confirmation
Chiller rooms temperature: 0 °C to +3 °C	Confirmed. Medium-temperature systems selected for 0 °C to +3 °C room temperature.
Freezer rooms temperature: -20 °C	Confirmed. Low-temperature systems selected and guaranteed for -20 °C room temperature.
Continuous design ambient temperature: 48 °C	Confirmed. All equipment selections are rated for 48 °C continuous ambient.
Outdoor unit working range: up to 52 °C condensing temperature	Confirmed. Condensing units are selected for operation up to 52 °C condensing temperature.
Refrigerant: new, environment-friendly, ASHRAE safety rating A1	R404A — a new-charge, non-flammable, non-toxic refrigerant with ASHRAE safety classification A1, widely serviced and available in Qatar for low- and medium-temperature commercial refrigeration. (GWP of R404A exceeds the tender's preferred value of 700 — refer to the Statement of Deviations / Clarifications, Section 8.)
Condensing units	DORIN (Italy) / EMERSON COPELAND / BITZER (Germany) — with semi-hermetic compressors. Three brand options are priced in the Commercial Bid.
Evaporator units	THERMOWAY / ICEMAKE / LuVe / FRIGA-BOHN — matched to the selected condensing units.
Outdoor heat exchanger: finned copper tubes with copper/aluminium fins, anticorrosive coating	Confirmed. Condenser coils with copper tubes and aluminium fins, factory anticorrosive coating suitable for the MIC industrial environment.
Control panel with instrumentation, temperature & humidity sensors; display of maintained temperature, humidity, set points, fan speed	Confirmed. One dedicated control panel per room with digital controller, temperature and humidity sensors, and display of room temperature, humidity, set points and fan status/speed.
Programmable periodic defrost cycle	Confirmed. Programmable defrost (electric for freezers; off-cycle/electric for chillers as applicable) via the room controller.
Individual main isolator/breaker per unit	Confirmed. Each indoor and outdoor unit provided with its own main isolator/breaker.
Field electrical wiring for indoor & outdoor units with proper breakers/isolators and safety cut-out relays, to industrial standards	Confirmed. Field power and control wiring between the Qatar Steel-provided power source points, the new panels and the units, with breakers/isolators and safety cut-outs, executed to industrial-quality workmanship.
Individual suction & discharge pressure gauges; HP/LP cut-in / cut-out differential relays per unit	Confirmed. Each unit fitted with suction and discharge pressure gauges and independent HP/LP safety pressure switches with cut-in/cut-out differential settings.
New refrigerant piping (suction & liquid) with proper insulation, industrial-quality workmanship	Confirmed. New copper suction and liquid lines, sized per selection, with closed-cell insulation and UV/mechanical protection where exposed.
Installation on proper vibration eliminators	Confirmed. All units mounted on vibration eliminators/anti-vibration pads; flexible connections at compressors as applicable.

Removal of existing units and termination of associated piping	Confirmed. Existing indoor/outdoor units dismantled, associated piping terminated safely and removed from site, with disposal as directed.
Commissioning to the full satisfaction of QS Engineers per the performance objectives	Confirmed. Full testing & commissioning including pressure/leak test, evacuation, charging, pull-down test to design room temperatures, and handover with commissioning report. Performance Guarantee Test per Clause 6.5 of the Draft Contract.
Warranty: one (1) year from date of commissioning	Confirmed. Twelve (12) months comprehensive warranty covering repair/replacement of parts or whole systems in the event of non-performance, including equipment failure (Section 6).
Gate passes & safety induction for the working team	Refer to Statement of Deviations / Clarifications (Section 8): MIC/QS gate pass fees are excluded; MES will attend QS HSE induction and comply with HSE regulations.

5. General Scope of Work (MES)

- Dismantling of the existing indoor and outdoor refrigeration units in all five (5) rooms and removal from site.
- Supply, installation, testing and commissioning of new refrigeration systems (indoor evaporators and outdoor condensing units with semi-hermetic compressors) with all associated accessories, using R404A refrigerant.
- Supply and installation of new refrigerant piping (suction and liquid lines), insulation, fittings and accessories between indoor and outdoor units.
- Supply and installation of new control panels for each room, including temperature and humidity sensors, digital display of room conditions and set points, and programmable defrost control where applicable.
- Supply and installation of new pressure relief devices (PRDs) for each cold room.
- Field electrical wiring and termination from the power source points provided by Qatar Steel to the new panels and equipment, including individual isolators/breakers per unit and safety cut-out relays.
- Supply and installation of two (2) new insulated cold-room doors with integrated heater frames for the two freezer rooms (single-leaf hinged type, clear opening 0.8 m × 1.8 m) — MES value addition.
- Provision of a suitable mobile crane for lifting and positioning of outdoor condensing units.
- Full testing and commissioning, including leak test, pull-down test and Performance Guarantee Test, with handover and commissioning report to the satisfaction of Qatar Steel Engineers.
- Attendance of Qatar Steel HSE safety induction by all deployed personnel and compliance with Qatar Steel HSE rules and regulations while working inside QS premises.

6. Delivery, Completion Schedule & Warranty

Delivery Basis	DDP Qatar Steel's Warehouse / Site, Mesaieed — as per Incoterms 2020.
Equipment Availability	Units are ex-stock in Qatar as of the date of this offer (subject to prior sale). Should stock be committed elsewhere, fresh factory order lead time is 2–3 months; early award is recommended.
Delivery Time	Ex-stock — delivery to site within one (1) week of order confirmation / advance receipt.

Installation & Commissioning Period	Fifteen (15) calendar days from site mobilization, inclusive of testing, commissioning and Performance Guarantee Test.
Warranty	Twelve (12) months from the date of successful commissioning, covering repair and replacement of part or whole of the systems in the event of non-performance, including equipment failure, under normal operating conditions (per Annexure-1, Scope of Work).

7. Exclusions

The following are excluded from our offer and, where required, shall be arranged by or at the cost of Qatar Steel:

- Qatar Steel / MIC site permit and gate pass fees and any associated government/authority charges (MES shall submit the required applications and personnel documents; pass fees, if any, are excluded).
- Civil, structural or builder's works (core drilling, openings, plinths, etc.).
- Replacement of cold-room insulated wall/ceiling panels or floors.
- Modification or replacement of upstream electrical infrastructure: power source, main distribution boards, and cabling upstream of the supply points provided by Qatar Steel (per Qatar Steel's scope in Annexure-1 — provision of power source for the new equipment).
- Any works required outside normal working hours on a premium basis, unless separately agreed.
- Any work or supply items not expressly listed in our scope above.

8. Statement of Compliance & Statement of Deviations

Tender No.: PW/01-2/CP/TDR-18/2026 — **Description:** Tender for Supply, Installation & Commissioning of Refrigeration Units for Cold Stores in Qatar Steel's Kitchen Facility

Having examined the complete Tender Document (Invitation, Instructions to Bidders, Annexure-1 Scope of Work, Annexure-2 Priced Offer Format, Statement of Compliance, Draft Contract and Form of Acknowledgement), we, the undersigned, offer to provide and complete the whole of the tendered Equipment and Services as per the prices quoted in our separately submitted Commercial Bid. We understand Qatar Steel is not bound to accept the lowest or any tender.

Our offer reference	MES/QTN/2026/0416-01 Rev.1
Our offer is valid till	Ninety (90) days from the tender closing date (i.e., up to 20 October 2026)
Delivery Terms	DDP Qatar Steel's Warehouse / Site, Mesaieed — Incoterms 2020
Delivery Time	Ex-stock; delivery within one (1) week of order confirmation (subject to prior sale)
Execution / Site Services Schedule	Fifteen (15) calendar days from site mobilization
Warranty Period	Twelve (12) months from date of successful commissioning
Tender Bond	Not Applicable (per tender)
Circulars considered	None received during the bidding stage

Compliance Status: ☒ **PARTIALLY COMPLIED** / ☐ Fully Complied

We hereby advise that our offer is in compliance with Qatar Steel's tender requirements — including the Scope of Supply and/or Services, technical specifications, Liquidated Damages, Insurance Requirements, Safety & Environment Protection Regulations, Medical Fitness Certificates and Guarantee & Warranty Terms — except for the deviations/clarifications listed below. We understand and confirm that any deviation mentioned elsewhere in the offer and not listed below shall not be considered by Qatar Steel and shall not be binding.

Statement of Deviations / Clarifications

No.	Tender / Contract Reference	MES Deviation / Clarification
1	Payment Terms — Instructions to Bidders Cl. 15(c) & Draft Contract Cl. 4.2 (100% within 30 days after delivery, completion & acceptance)	MES payment terms: Seventy percent (70%) advance payment upon order confirmation; thirty percent (30%) upon successful completion, commissioning and handover. This is required to secure the ex-stock units and covers procurement of the equipment.
2	Annexure-1, Scope item 14 — Contractor to arrange gate passes	MES shall prepare and submit all gate pass applications and personnel/vehicle documents for its team; however, any MIC/QS gate pass fees or authority charges are excluded from our price and shall be reimbursed at cost or arranged by Qatar Steel.
3	Annexure-1 — General Specification, refrigerant preferably GWP < 700	Offered refrigerant is R404A (ASHRAE safety class A1, non-flammable, new charge). Its GWP exceeds the preferred value of 700. R404A is offered for its proven reliability at -20 °C duty, availability of charge and service support in Qatar, and compatibility with the offered semi-hermetic condensing unit ranges. Alternative lower-GWP selections can be offered on request, subject to price and delivery adjustment.
4	Draft Contract Cl. 9.5 — Warranty from date of Acceptance Certificate	Warranty of twelve (12) months shall commence from the date of successful commissioning, in line with Annexure-1 (Scope of Work — Warranty and Local Support).

For Metri Engineering Services W.L.L.

Eng. Fayez Metri

Managing Director | Mob: +974 5557 2793 | mes@mes.qa

