

TECHNICAL & COMMERCIAL PROPOSAL

COLD ROOMS

Design, Supply, Installation, Testing & Commissioning

Project:	Transsind Food Facility
Location:	Doha, Qatar
Scope:	Freezer Rooms 1–5 & Chilled Corridor
Reference:	MES/PROP/TFF-CR/2026-696
Date:	April 2026
Validity:	15 Days from Date of Issue

1. EXECUTIVE SUMMARY

Metri Engineering Services W.L.L. (MES) is pleased to submit this Technical and Commercial Proposal for the Design, Supply, Installation, Testing and Commissioning of the complete cold room system at the Transsind Food Facility, Doha, Qatar.

The scope encompasses five (5) freezer rooms and one (1) chilled corridor, comprising a total refrigerated volume of approximately 12,950 cubic metres. The system is designed for frozen food storage at -20°C (Cold Rooms 1–4), deep-frozen storage at -25°C (Cold Room 5), and chilled product handling at +5°C (Corridor), all engineered for the extreme ambient conditions of Qatar (46°C summer design).

MES brings over 35 years of HVAC, refrigeration, and MEP engineering experience in Qatar, serving major clients across industrial, commercial, and food processing sectors.

2. SCOPE OF WORK

The following scope of work is included in this proposal:

2.1 Freezer Rooms & Related Corridor Area Refrigeration Systems

Complete design, supply, installation, testing, and commissioning of the refrigeration systems serving all five (5) freezer cold rooms and one (1) chilled corridor. This includes air-cooled condensing units, matched evaporator units, complete refrigeration copper piping with insulation, expansion valves, solenoid valves, filter driers, sight glasses, oil separators, check valves, pressure regulators, and all required refrigeration accessories. Each room is served by independent condensing unit(s) and evaporator(s) as detailed in the equipment schedule.

2.2 Insulated Cold Store Sandwich Panels (PIR)

Supply and installation of Polyisocyanurate (PIR) sandwich panels, 150mm thickness, for all cold room walls and ceilings. Panels with tongue-and-groove jointing system. All joints shall be sealed using sealant to ensure vapour-tight enclosure integrity. Includes all flashings, trims, corner pieces, and support brackets.

2.3 Manual Sliding Doors & Hinged Doors

Supply and installation of cold room access doors as follows: seven (7) single-leaf hinged doors and six (6) manual sliding doors, all manufactured from PIR sandwich panels. Freezer room doors to include heated door frames to prevent ice build-up, full perimeter gaskets, internal safety release handles, and observation windows. Sliding doors to include heavy-duty overhead track system with smooth manual operation.

2.4 Floor Insulation (XPS Polystyrene)

Supply and installation of 100mm extruded polystyrene (XPS) medium-density floor insulation boards for all cold rooms and corridor. Includes vapour barrier membrane installation beneath the insulation layer. Note: Concrete topping and floor finishes are excluded and are by others.

2.5 LED Lights for Cold Rooms

Supply and installation of LED cold-room rated lighting fixtures (IP65 rated, low-temperature rated) within all freezer rooms and the chilled corridor.

2.6 Control Panels & Commissioning

Supply and installation of control panels for each cold room incorporating digital temperature controllers, high/low pressure safety switches, defrost timers, door switches. Full testing, commissioning, and performance verification of all systems.

3. EQUIPMENT ORIGINS & APPROVED BRANDS

#	Item	Approved Brands	Origin
1	PIR Sandwich Panels	—	Made in Qatar approved by QCDD
2	Manual Sliding Doors & Hinged Doors	—	Made in Turkey or KSA
3	Floor Insulation (XPS)	—	Made in Qatar
4	Air-Cooled Condensing Units	BITZER or COPELAND	European
5	Evaporator Units	GÜNTNER or SEARLE KELVION or LUVE	European

4. ROOM SCHEDULE

#	Room	Temp °C	Width mm	Depth mm	Height m	Area m ²	Vol. m ³	Doors
1	Cold Room 1 (Freezer)	-20	21,100	8,160	10	172	1,722	1H+1S
2	Cold Room 2 (Freezer)	-20	21,100	8,505	10	179	1,795	1H+1S
3	Cold Room 3 (Freezer)	-20	21,100	11,500	10	243	2,427	1H+1S
4	Cold Room 4 (Freezer)	-20	21,100	11,650	10	246	2,458	1H+1S
5	Cold Room 5 (Deep Freezer)	-25	21,100	13,000	10	274	2,743	1H+1S
6	Corridor (Chilled)	+5	4,875	52,880	7	258	1,805	2H+1S

5. COMMERCIAL PROPOSAL

5.1 Lump Sum Price

Design, Supply, Installation, Testing & Commissioning	LUMP SUM PRICE
Complete Cold Room System for Transsind Food Facility as detailed in this proposal, including all freezer rooms (1–5), chilled corridor, insulated panels, doors, floor insulation, refrigeration equipment, LED lighting, controls, and commissioning.	QAR 2,750,000/- <i>(Qatari Riyals Two Million Seven Hundred Fifty Thousand Only)</i>

The above lump sum price is firm and includes all materials, equipment, labour, transportation, site facilities, testing, commissioning, and handover as described in the scope of work. All applicable taxes and duties are included.

6. EXCLUSIONS

Our scope does not include civil works, removal of existing units, steel base frames / foundation for condensers, machine room, closed working room and storage on site, electrical power supply on site during installation, plumbing and sanitary works, electrical sub-distribution panel in machinery room, electrical connection between sub-distribution panel and our control panels, insurance policy, governmental fees, any other related additional costs and any supplies and services not especially listed herein.

Without limitation, the following items are explicitly excluded:

1. All kinds of civil works including passage/sleeve for refrigerant pipes through the walls, etc.
2. Electrical power supply and earthing to our control panels.
3. Drain points as required.
4. Foundation or steel platforms for the condensers.
5. Adequate safe storage area for all equipments and materials (for turnkey jobs).
6. Temporary water and electricity during installation (for turnkey jobs).
7. Disposal and carting away of sundry items.
8. Offloading of materials at site.
9. Any Quality Testing Procedure at site.
10. Any third party approvals.
11. Factory visits.
12. Dosing system (water treatment) for the evaporative condensers.
13. Any other item/service not specifically mentioned herein.
14. Any special specifications other than the standard.
15. Any pipe ventilation works.
16. Concrete works or floor finishes (concrete topping over XPS is by others).
17. Any steel platform to hang the outdoor/indoor units.

18. Any civil works and plinths.
19. Any electrical works (power supply, cabling, distribution boards, earthing — all by Electrical Contractor).
20. Fire detection and firefighting systems within cold rooms.
21. Building Management System (BMS) integration.
22. Racking and shelving systems within cold rooms.
23. Floor heating system for frost-heave prevention.

7. TERMS & CONDITIONS

7.1 Payment Terms

50% — Advance payment upon signing of contract / Letter of Award.

20% — Upon delivery of insulated panels to site.

20% — Upon delivery of refrigeration equipment to site.

5% — Upon completion of installation and mechanical completion.

5% — Upon successful commissioning and handover.

7.2 Project Timeline

Total Estimated Duration: 18–22 weeks from Letter of Award.

7.3 Warranty

Twelve (12) months Defects Liability Period (DLP) from the date of successful commissioning and handover. The warranty covers defects in materials and workmanship under normal operating conditions. Compressors carry manufacturer warranty as per Bitzer/Copeland standard terms. Evaporator units carry manufacturer warranty as per Güntner/Searle Kelvion/LUVE standard terms.

7.4 Validity

This proposal is valid for (15) calendar days from the date of issue. Prices are subject to review beyond the validity period due to potential fluctuations in material costs and exchange rates.

7.5 General

All works shall comply with applicable Qatar Construction Specifications (QCS), ASHRAE standards, and local authority requirements. MES shall coordinate with other contractors (civil, electrical) as required for the successful completion of the works. The Client shall ensure timely access to the site, provision of power and water for installation, and coordination of enabling works by others.

We trust this proposal meets your requirements and look forward to your favorable consideration.

For and on behalf of

METRI ENGINEERING SERVICES W.L.L.



Eng. Fayez Metri (55572793)

