TECHNICAL & COMMERCIAL PROPOSAL

For the Design, Supply, Installation, Testing & Commissioning of

OPTION#1 (CONCEALED DUCT SPLIT & WALL MOUNTED SPLIT)
OPTION#2 (VRF CONCEALED DUCT SPLIT & VRF WALL MOUNTED SPLIT)

CLIENT:	**Mr. Abdulla Al Kaabi**
PROJECT:	**Private Villa G+1+PH**
DATE:	09 April 2026
REFERENCE:	MES/QT/2026/04-426-rev3

Dear Sir, With reference to the architectural drawings and request sent to us, please find below:

1. SCOPE OF WORK

MES Qatar is pleased to submit this proposal for the complete design, supply, installation, testing, and commissioning of Duct Split and Wall Mounted Split Air Conditioning systems for Mr. Abdulla Al Kaabi's Private Villa.

Brand: Mitsubishi Electric
Equipment Types: Duct Split & Wall Mounted Split AC Units

Scope Includes:

- Design phase
- PIR Ductwork for concealed type AC units with air outlets
- Indoor and outdoor units with remote controls
- Refrigerant piping (copper) with insulation
- Drain piping and termination
- Complete installation and commissioning

2. EQUIPMENT SCHEDULE & PRICING

OPTION#1 (CONCEALED DUCT SPLIT & WALL MOUNTED SPLIT)

Area	AC Type	Qty	AREA SERVED	kW @46°C	Total Price
Ground Floor	Duct Split	1	Majlis	20.61	QAR 40,000
Ground Floor	Duct Split	1	Sitting+ Entrance Hall	20.61	QAR 40,000
Ground Floor	Duct Split	1	Family Sitting + lift lobbby	11.90	QAR 24,560
Ground Floor	Duct Split	1	Pantry + Family Dining	11.90	QAR 24,560

Area	AC Type	Qty	AREA SERVED	kW @46°C	Total Price
Ground Floor	Duct Split	1	Office	9.55	QAR 21,000
Ground Floor	Duct Split	1	Corridor	9.55	QAR 21,000
First Floor	Duct Split	1	Master Bedroom+Ladies Dress + Gents Dress+Corridor	26.01	QAR 45,700
First Floor	Duct Split	1	Family Sala + Corridor	11.90	QAR 24,560
First Floor	Duct Split	1	Bedroom + Dress	9.55	QAR 21,000
First Floor	Duct Split	1	Bedroom + Dress	9.55	QAR 21,000
First Floor	Duct Split	1	Bedroom + Dress	9.55	QAR 21,000
First Floor	Duct Split	1	Bedroom + Dress	7.90	QAR 14,500
First Floor	Duct Split	1	Corridor	7.90	QAR 14,500
First Floor	Duct Split	1	Main Hall double height	14.95	QAR 27,500
Penthouse	Wall Split	5	MS-GS30 / MU-GS30 2.5T	8.20	QAR 31,250
Penthouse	Wall Split	1	MS-GS18 / MU-GS18 1.5T	4.7	QAR 3,900
Outside Kitchen	Wall Split	3	MS-GS18 / MU-GS18 1.5T	4.7	QAR 11,700
Outside Kitchen	Wall Split	1	MS-GS24 / MU-GS24 2T	5.90	QAR 9,000
DRIVER ROOM	Wall Split	1	MS-GS18 / MU-GS18 1.5T	4.7	QAR 3,900
				GRAND TOTAL (Design, Supply & Installation)	**QAR 420,630**

Amount in Words: *Qatari Riyals Four Hundred Twenty Thousand Six Hundred Thirty Only*

OPTION#2 (VRF CONCEALED DUCT SPLIT & VRF WALL MOUNTED SPLIT)

Area	AC Type	Qty	AREA SERVED	kW @46°C	Total Price
Ground Floor	VRF CONCEALED DUCT SPLIT	1	Majlis	20.61	QAR 56,000
Ground Floor	VRF CONCEALED DUCT SPLIT	1	Sitting+ Entrance Hall	20.61	QAR 56,000
Ground Floor	VRF CONCEALED DUCT SPLIT	1	Family Sitting + lift lobbby	11.90	QAR 34,384
Ground Floor	VRF CONCEALED DUCT SPLIT	1	Pantry + Family Dining	11.90	QAR 34,384
Ground Floor	VRF CONCEALED DUCT SPLIT	1	Office	9.55	QAR 29,400
Ground Floor	VRF CONCEALED DUCT SPLIT	1	Corridor	9.55	QAR 29,400
First Floor	VRF CONCEALED DUCT SPLIT	1	Master Bedroom+Ladies Dress + Gents Dress+Corridor	26.01	QAR 63,980
First Floor	VRF CONCEALED DUCT SPLIT	1	Family Sala + Corridor	11.90	QAR 34,384

Area	AC Type	Qty	AREA SERVED	kW @46°C	Total Price
First Floor	VRF CONCEALED DUCT SPLIT	1	Bedroom + Dress	9.55	QAR 29,400
First Floor	VRF CONCEALED DUCT SPLIT	1	Bedroom + Dress	9.55	QAR 29,400
First Floor	VRF CONCEALED DUCT SPLIT	1	Bedroom + Dress	9.55	QAR 29,400
First Floor	VRF CONCEALED DUCT SPLIT	1	Bedroom + Dress	7.90	QAR 20,300
First Floor	VRF CONCEALED DUCT SPLIT	1	Corridor	7.90	QAR 20,300
First Floor	VRF CONCEALED DUCT SPLIT	1	Main Hall double height	14.95	QAR 38,500
Penthouse	VRF CONCEALED DUCT SPLIT	5	SALAH+BEDROOM+CORRIDOR+HOME SALON	8.20	QAR 68,770
Penthouse	VRF CONCEALED DUCT SPLIT	1	LAUNDRY+IRON	4.7	
Outside Kitchen	Wall Split	3	MS-GS18 / MU-GS18 1.5T	4.7	QAR 11,700
Outside Kitchen	Wall Split	1	MS-GS24 / MU-GS24 2T	5.90	QAR 9,000
DRIVER ROOM	Wall Split	1	MS-GS18 / MU-GS18 1.5T	4.7	QAR 3,900
				GRAND TOTAL (Design, Supply & Installation)	**QAR 598,602**

Amount in Words: *Qatari Riyals Five Hundred Ninety-Eight Thousand Six Hundred Two Only*

3. TERMS & CONDITIONS

Delivery & Installation:

- 3 months from order confirmation and site readiness

Payment Terms:

- 50% Advance upon order confirmation
- 30% Upon delivery of equipment to site
- 15% After completion of installation
- 5% Against testing & commissioning

Warranty:

- 1 Year warranty on complete unit
- 4 Additional years on compressor only against manufacturing defects
- *Manufacturer Warranty Policy Applies*

4. ASSUMPTIONS

- Electrical points and drain points are provided within 1 meter from installation location
- Scope excludes any civil works, electrical works, special scaffolding, or power upgrades

5. GENERAL EXCLUSIONS

1. Civil works (e.g., cutting, patching, wall openings)
2. Electrical cabling and isolator supply
3. Any ceiling works (beyond scope)
4. Temporary Power source supply for testing
5. Exhaust fans, unless mentioned
6. Debris removal or site clearance
7. Any items not specifically included above
8. Any VAT charges imposed by authorities at a later stage
9. Any Utility/Authorities fees
10. Any inspection, approval fees, and utilities
11. Any crane for loading/offloading at site
12. Temporary power supply at site

6. QUOTATION VALIDITY

This quotation is valid for **15 working days** from the issue date and is subject to confirmation thereafter.

Metri Engineering Services W.L.L
+974 4445 9207 / 5557 2793
mes@mes.qa
www.mes.qa

متري للخدمات الهندسية ذ.م.م
ص.ب: ١٩٩٦٢ الدوحة - قطر
تليفكس: ٤٤١٢٧٦٧
P.O. Box 19962, Doha-Qatar
TelFax: 4412767
METRI ENGINEERING SERVICES W.L.L