

ALTERNATIVE QUOTATION

Quotation Ref. No.: MES/QTN/HVAC/ESM/2026-195A

Date: 25 August 2026

To:

M/s EBN SINA MEDICAL

State of Qatar

Kind Attention: Mr. Yasser Al Attar

Subject: Design, Supply and Installation of a Standby (Back-up) Air Conditioning System for Warehouse WH-1

Project: Back-up AC for Warehouse WH-1

Dear Mr. Yasser,

With reference to our recent discussion and further to our offer Ref. MES/QTN/HVAC/ESM/2026-195 dated 15 August 2026, we are pleased to submit this alternative technical and commercial offer for the design, supply and installation of a dedicated stand-by air conditioning system and dehumidifier for Warehouse WH-1.

The proposed system is intended to eliminate the recurring rise in internal temperature experienced during the hot season, and importantly to maintain the required storage conditions whenever the existing air conditioning system is shut down for repair, servicing or planned maintenance. The system has been configured so that all installation works are executed from outside the warehouse, with no disturbance to your ongoing storage operations. This alternative offer is based on a 28.5 TR packaged unit and, as an option, a standalone industrial dehumidifier installed inside the warehouse.

1. PROPOSED SOLUTION

We propose the installation of a packaged air conditioning unit of 28.5 TR cooling capacity, located externally and connected to the warehouse through an insulated air distribution system, as follows:

- The package AC unit is installed outside the warehouse on a concrete plinth, complete with anti-vibration mountings.
- Supply and return air ducting is fabricated from 30 mm thick PIR (polyisocyanurate) sandwich panels with self aluminum cladding, suitable for external installation under Qatar climatic conditions.
- The duct route is fixed externally along the warehouse wall at approximately 5.00 m height on hot-dip galvanised steel supports and brackets, so that no ductwork occupies the internal storage volume.
- Air is delivered into the space through four (4) numbers supply air grilles, positioned to achieve uniform air distribution across the warehouse, with one (1) number return air grille to complete the air circuit.
- The unit operates fully independently of the existing air conditioning system. In the event of failure, shutdown or repair works on the main system, the back-up package unit is brought into operation — either manually or automatically — to maintain the space temperature.

This arrangement provides the ideal and most practical solution to the problem of temperature rise during the hot season and during maintenance or repair shutdowns, while keeping all installation activity outside the operational storage area.



2. SCOPE OF WORK

Item	Activity	Description
3.1	Design & Engineering	equipment selection, duct sizing and air distribution design, preparation of shop drawings and layouts for your review and approval.
3.2	Supply of Equipment	Supply & Installation of one (1) No. packaged air conditioning unit of 28.5 TR nominal cooling capacity. Brand: SKM or FRIMEC or YORK. Electrical power input 43 kW, 3-phase, 415 V, 50 Hz.
3.3	Air Distribution System	Fabrication and installation of supply and return air ducting in 30 mm PIR sandwich panels suitable for exposed weather, including all fittings, transitions, sealing, dampers and accessories.
3.4	Support Steelwork	Supply and installation of galvanized steel supports, brackets and hangers for fixing the duct run along the external warehouse wall at approximately 5.00 m height.
3.5	Grilles	Supply and installation of four (4) Nos. supply air grilles with volume control dampers and one (1) No. return air grille.
3.6	Civil Works	Concrete plinth / foundation for the packaged unit, wall openings for duct penetrations, making good, sealing and weatherproofing of all penetrations. (Included in the quoted price.)
3.7	Testing & Commissioning	Full testing, air balancing of the supply grilles, commissioning of the unit and verification of the achieved space temperature.
3.8	Handover	Handover of the system in full working condition, together with operating instructions and equipment documentation, and demonstration of the changeover operation to your maintenance personnel.

3. TECHNICAL

Description	Particulars
System type	Packaged air conditioning unit — air cooled, ducted, externally mounted
Nominal cooling capacity	28.5 TR (≈ 342,000 BTU/hr • ≈ 100 kW)
Brand / make	SKM or FRIMEC or YORK
Electrical power input	43 kW, 3-phase, 415 V, 50 Hz (by others — refer Exclusions)
Quantity	One (1) No.
Location of unit	External — outside the warehouse, on concrete plinth with anti-vibration mounts
Ductwork	PIR sandwich panel, 30 mm thick, aluminium cladding both faces
Duct routing	External, fixed along warehouse wall at approximately 5.00 m height
Supply air grilles	Four (4) Nos., aluminium, with volume control dampers
Return air grille	One (1) No., aluminium
Mode of operation	Stand-by / back-up duty — manual or automatic start-up
Installation method	All works executed from outside the warehouse — no disturbance to stored goods or internal operations

4. COMMERCIAL OFFER

Our lump sum price for the complete scope of work described above, including all civil works, is as follows:

Sl.	Description	Amount (QAR)
1	Design, supply and installation of back-up air conditioning system for Warehouse WH-1 — 28.5 TR package AC unit (SKM / FRIMEC / YORK), PIR sandwich panel ducting with aluminium cladding, support steelwork, supply and return air grilles, controls, testing and commissioning — including all civil works	167,000.00
	Less: Special Discount	(19,000.00)
	NET TOTAL PRICE	148,000.00

Amount in words: Qatari Riyals One Hundred Forty-Eight Thousand Only (QAR 148,000.00)

The above price is a firm lump sum covering the complete supply and installation of the system, including all associated civil works.

5. OPTIONAL ADDITION — STANDALONE INDUSTRIAL DEHUMIDIFIER

In addition to the back-up cooling system offered above, and further to our discussion, we are pleased to offer as an option one (1) No. standalone industrial dehumidifier, brand FREGO, of 360 litres/day moisture removal capacity, installed inside Warehouse WH-1, as follows:

- The dehumidifier is a self-contained industrial floor-standing unit of 360 L/day capacity, positioned inside the warehouse at a location agreed with your operations team. It operates independently of the ductwork, so no modification to the air distribution system is required.
- The unit is complete with a built-in humidistat with adjustable set point. It can be operated manually, or set to start and stop automatically once the relative humidity inside Warehouse WH-1 rises above the pre-set value.
- Working together with the back-up package AC unit, the system holds the storage environment stable — the AC controlling the space temperature and the dehumidifier controlling the relative humidity — both during peak summer conditions and during any shutdown, repair or maintenance of the main air conditioning system.
- This safeguards the stored goods against the effects of high humidity, such as condensation on packaging, damage to cartons and labels, and deterioration of moisture-sensitive products.
- Being a standalone machine, the unit requires only an electrical power supply of **8 kW, 3-phase, 415 V, 50 Hz** and a condensate drain connection. Installation is rapid, the unit can be repositioned within the warehouse if required, and there is minimal disturbance to your ongoing operations.

Our price for this optional additional scope is as follows:

Sl.	Description	Amount (QAR)
2	Supply and installation of one (1) No. standalone industrial dehumidifier, brand FREGO, 360 litres/day capacity, complete with built-in humidistat, condensate drain connection and accessories, installed inside Warehouse WH-1 — including testing and commissioning	22,000.00
	Less: Special Discount	(4,000.00)
	NET PRICE — OPTIONAL STANDALONE DEHUMIDIFIER	18,000.00

Amount in words: Qatari Riyals Eighteen Thousand Only (QAR 18,000.00)

This item is offered as an option and is priced in addition to the base offer under Section 5. Should both be taken together, the combined net price is QAR 166,000.00 (Qatari Riyals One Hundred Sixty-Six Thousand Only).

6. EXCLUSIONS

The following are specifically excluded from our offer:

- **Electrical works** — including power supply, main and sub distribution boards, circuit breakers, power cabling, cable trays, earthing and final power connection to the units. For reference, the required power input is 43 kW (3-phase, 415 V, 50 Hz) for the package AC unit and 8 kW (3-phase, 415 V, 50 Hz) for the optional dehumidifier.
- Any authority approvals, permits, NOCs or associated fees.
- Any modification, repair or upgrading works to the existing air conditioning system.
- Fire alarm integration, fire fighting, BMS integration or any works not expressly listed under Section 3.
- Anything not mentioned clearly.

7. PAYMENT TERMS

Stage	Milestone	Percentage
1	Advance payment against issuance of Purchase Order / Letter of Award	50 %
2	Against delivery of the packaged unit and panel materials to site	40 %
3	Against completion of installation, testing, commissioning and handover	10 %

8. GENERAL TERMS & CONDITIONS

Validity of offer	Thirty (30) days from the date of this quotation.
Delivery & completion	(4) weeks from the date of receipt of the Purchase Order, technical approvals and advance payment.
Warranty	Twelve (12) months from the date of handover against manufacturing defects and defective workmanship, under normal operating conditions.
Client's scope	Provision of free and safe access to the works area, storage/lay-down area at site, and the complete electrical power supply and final connection to the unit as noted under Exclusions.
Prices	Quoted in Qatari Riyals (QAR), exclusive of any taxes or levies imposed by the authorities. Any variation in scope shall be quoted and agreed separately.

We trust that the above offer meets with your requirements and provides the reliable back-up solution required for Warehouse WH-1. Should you wish to discuss any technical or commercial aspect of this proposal, or require a site visit to finalise the duct routing and grille positions, we shall be pleased to attend at your convenience.

We thank you for the opportunity to quote and look forward to your valued order.

Yours faithfully,

METRI ENGINEERING SERVICES W.L.L.

