METRI ENGINEERING SERVICES W.L.L
متري للخدمات الهندسية ذ.م.م

TECHNICAL & COMMERCIAL PROPOSAL

FOR

1-YEAR SERVICE AGREEMENT

FCU, AHU, AND SPLIT UNIT MAINTENANCE

ALL QATAR COOL PLANTS

P1, P2, P3, IDCP, TPQ-Hex, Gewan

SUBMITTED TO:

Qatar District Cooling Company (Qatar Cool)
P.O. Box 24979, Doha, Qatar

Proposal Reference: MES/QC-HVAC/2026-219
Date: 25 February 2026 | Validity: 30 Days

Tel: 44459207 - Fax: 44780499 - P.O.Box: 23107
E-mail: mes@mes.qa - Web: www.mes.qa

1. EXECUTIVE SUMMARY

Metri Engineering Services (MES) is pleased to submit this Technical and Commercial Proposal in response to Qatar Cool's Request for Quotation for a 1-Year Service Agreement covering the maintenance of FCU, AHU, and Split Units across all Qatar Cool plants (P1, P2, P3, IDCP, TPQ-Hex, and Gewan).

MES is an established engineering company based in Qatar with extensive experience in HVAC maintenance, Testing Adjusting & Balancing (TAB), duct cleaning, and facility management services. We have proudly served major clients including QatarEnergy, HASSAD, EBN SINA MEDICAL, Qatar Airways, and GWC.

Key Highlights:

- Full compliance with Qatar Cool's Scope of Work requirements
- 4 service visits per year: 3 Quarterly + 1 Annual (comprehensive deep service)
- Capability to deploy multiple crews simultaneously across all plant locations
- Emergency response as per contractual requirements
- HSE compliance

2. UNDERSTANDING OF SCOPE

MES has thoroughly reviewed the Scope of Work (SOW), Bill of Quantities (BOQ), and all tender documents provided by Qatar Cool. We confirm our complete understanding of the project requirements.

2.1 Project Overview

Contract Type	Long-Term Service Agreement (LTSA)
Contract Duration	1 Year (with potential 2+2 extension)
Service Locations	P1, P2, P3, IDCP, TPQ-Hex, Gewan (6 locations)
Nature of Work	Critical
Service Frequency	4 visits/year: 3 Quarterly (Q1, Q2, Q3) + 1 Annual (Q4)

2.2 Equipment Summary

Plant	FCU	AHU	Split	Total
P1	21	4	-	**25**
P2	30	3	-	**33**
P3	13	3	5	**21**
IDCP	28	5	1	**34**
TPQ-Hex	38	-	-	**38**
Gewan	27	4	-	**31**
TOTAL	**157**	**19**	**6**	**182**

Note: TPQ-Hex units are located outside IDCP plant within a 2km radius.

2.3 Equipment Details

- FCUs: Mix of Direct Drive and Belt Drive types, Ceiling and Wall mounted
- AHUs: Carrier 39FX and Euroclima ZHK models with bag filters
- Split Units: Carrier models in P3 and IDCP locations

3. TECHNICAL APPROACH & METHODOLOGY

3.1 Service Visit Structure

Each unit will receive 4 service visits per year structured as follows:

Visit	Type	Scope
Q1	Quarterly PM	Standard preventive maintenance tasks
Q2	Quarterly PM	Standard preventive maintenance tasks
Q3	Quarterly PM	Standard preventive maintenance tasks
Q4	**Annual PM**	Comprehensive deep service (includes all quarterly tasks + additional annual tasks)

3.2 Quarterly Maintenance Tasks (Q1, Q2, Q3)

FCU Tasks:

- Check, clean, and retighten all fasteners
- Check pulley tightness and alignment (belt-drive units)
- Check and retension belts as required
- Check rotational wobbling condition of the impeller
- Motor IR test and electrical terminal inspection
- Clean coil with normal water pressure
- Clean drain pan with normal water pressure
- Clean panel filter with normal water pressure

AHU Tasks:

- Check and clean unit casings
- Check tightness of set screw blower wheel and pulley
- Check, clean, align, and retension belts
- Clean panel filter and bag filter
- Clean Y-strainer and drain pan
- Check antifrost thermostat
- Regrease motor bearings
- Clean coil with normal water pressure

3.3 Annual Maintenance Tasks (Q4 - Additional to Quarterly)

- Deep chemical coil cleaning (evaporator and condenser)
- Fan wheel inspection and cleaning
- Complete motor mechanical and electrical inspection
- Drain pan disinfection and flushing
- Performance and airflow verification

- Repair damaged coil fins (hot/cold work where possible)

3.4 Response Time Commitment

Condition	Response Time	MES Commitment
Emergency	2 Hours	24/7 Emergency hotline with on-call technicians
Urgent	24 Hours	Response within 24 hrs, mobilize within 48 hrs
Routine	3 Working Days	Per approved maintenance schedule

4. RESOURCE & MANPOWER PLAN

MES will deploy a dedicated team capable of simultaneous operations across all Qatar Cool plant locations, ensuring no dependency on task completion at other sites.

5. HSE COMPLIANCE & QUALITY ASSURANCE

5.1 HSE Commitments

- Zero Lost Time Incidents (LTI) target
- 100% Permit to Work (PTW) compliance
- All personnel to complete Qatar Cool HSE safety induction prior to site access
- Full PPE compliance: Safety vests, helmets, and safety shoes at all times
- Daily toolbox talks before commencement of work
- PTW applications submitted minimum 1 week prior to activities

5.2 Reporting Requirements

Report Type	Contents
PM Report	Work description, defects identified, actions taken, before/after photos, checklist
CM Report	Work description, observations, corrective actions, before/after photos
BM Report	Fault description, root cause analysis, actions taken, spare parts used, photos

All reports will be submitted within 7 working days of task completion.

6. COMMERCIAL PROPOSAL

MES is pleased to submit the following commercial offer. All prices are in Qatari Riyals (QAR), exclusive of VAT, and represent PREVENTIVE MAINTENANCE for 4 service visits per year (3 Quarterly + 1 Annual).

6.1 FCU Preventive Maintenance Pricing

Plant	Qty	Q Rate	A Rate	3Q Total	1A Total	Subtotal
P1	21	150	250	6,300	5,250	11,550
P2	30	150	250	9,000	7,500	16,500
P3	13	150	250	3,900	3,250	7,150
IDCP	28	150	250	8,400	7,000	15,400
TPQ-Hex	38	150	250	11,400	9,500	20,900
Gewan	27	150	250	8,100	6,750	14,850
FCU TOTAL	**157**			**70,650**	**39,250**	**109,900**

6.2 AHU Preventive Maintenance Pricing

Plant	Qty	Q Rate	A Rate	3Q Total	1A Total	Subtotal
P1	4	350	650	4,200	2,600	6,800
P2	3	350	650	3,150	1,950	5,100
P3	3	350	650	3,150	1,950	5,100
IDCP	5	350	650	5,250	3,250	8,500
Gewan	4	350	650	4,200	2,600	6,800
AHU TOTAL	**19**			**19,950**	**12,350**	**32,300**

6.3 Split Unit Preventive Maintenance Pricing

Plant	Qty	Q Rate	A Rate	3Q Total	1A Total	Subtotal
P3	5	100	200	1,500	1,000	2,500
IDCP	1	100	200	300	200	500
SPLIT TOTAL	**6**			**1,800**	**1,200**	**3,000**

6.4 Breakdown Maintenance Rates (Labor Only)

Item	Description	Unit	Rate (QAR)/HR
B1	Breakdown call-out (Normal Hours: 7AM-5PM)	Call	250
B2	Breakdown call-out (After Hours / Weekend / Holiday)	Call	400
B3	Replacement of FCU motor (labor only)	Each	350
B4	Replacement of AHU motor (labor only)	Each	650
B5	Replacement of FCU coil (labor only)	Each	500
B6	Replacement of AHU coil (labor only)	Each	1,200
B7	Replacement of complete FCU unit (labor only)	Each	800
B8	Replacement of complete AHU unit (labor only)	Each	2,500
B9	Replacement of structural casing FCU (labor only)	Each	400
B10	Replacement of structural casing AHU (labor only)	Each	1,000
B11	Drainline declogging (AHU/FCU)	Each	100

6.5 Spare Parts Pricing

Spare parts pricing (as per BOQ sheets for Fast-Moving Consumables, Operational Spares, and Major Items) will be provided upon request based on actual specifications and quantities required. Pricing will be quoted on a case-by-case basis with competitive market rates and confirmed lead times.

6.6 Annual Contract Summary

Description	Amount (QAR)
FCU Maintenance (157 units: 3Q × 150 + 1A × 250)	109,900
AHU Maintenance (19 units: 3Q × 350 + 1A × 650)	32,300
Split Unit Maintenance (6 units: 3Q × 100 + 1A × 200)	3,000
TOTAL CONTRACT VALUE (1 YEAR) - LABOR ONLY	**QAR 145,200**

7. EXCLUSIONS & CLARIFICATIONS

The following items are EXCLUDED from the above pricing and shall be charged separately or provided by Qatar Cool:

7.1 Spare Parts & Consumables (EXCLUDED)

- All spare parts including filters (panel filters, bag filters), belts, motors, coils, bearings, pulleys, etc.
- Replacement materials required during Annual Maintenance tasks (filter replacement, belt replacement, insulation replacement)
- Consumables such as refrigerant top-up, chemicals, lubricants beyond standard maintenance quantities
- Spare parts pricing available on request per actual specifications

7.2 Lifting Equipment for High Units (EXCLUDED)

- Mobile Elevated Work Platforms (MEWP / Scissor Lifts / Boom Lifts)
- Cranes or specialized lifting equipment for heavy components
- Access equipment beyond standard scaffolding and ladders
- *Note: Standard scaffolding and A-frame ladders are INCLUDED in our rates*

7.3 Other Exclusions

- Major equipment replacement or capital improvements
- Repair of damage caused by third parties, misuse, or force majeure
- Structural modifications to buildings or plant areas
- BMS/Controls programming or upgrades
- Any scope not explicitly mentioned in this proposal

7.4 Clarifications

1. Annual Maintenance rates include cleaning tasks only; replacement of filters, belts, and insulation materials are at additional cost
2. Breakdown maintenance rates are labor-only; spare parts will be quoted separately based on actual requirements
3. For units requiring MEWP or specialized lifting equipment, rental costs will be quoted upon site survey during mobilization

9. TERMS & CONDITIONS

9.1 Validity

This proposal is valid for 30 days from the date of submission.

9.2 Payment Terms

- MES accepts Qatar Cool's standard payment term of 30 days net from invoice submission
- Invoices will be submitted monthly based on completed maintenance activities
- All invoices will be accompanied by completion reports as per SOW requirements

9.3 Warranty

MES provides a 90-day warranty on all services from the date of final acceptance. This warranty covers defects resulting from workmanship only.

We thank Qatar Cool for this opportunity to submit our proposal and look forward to working together. MES is committed to delivering exceptional HVAC maintenance services.

Best Regards,

Metri Engineering Services W.L.L
Eng. Fayez 55572793