To	M/s Zad Holding Company Q.P.S.C.	**Quotation No.**	MES/QTN/2026/ZAD-EF-01
Attention	Mr. Vishnu Prasad	**Date**	01 October 2026
Email	vishnu@qfm.qa	**Validity**	30 days
Location	Oil Refinery Production Area — Ground Floor & Second Floor	**Revision**	00

QUOTATION

Supply & Installation of High Temperature Axial Wall Mounted Fans

Dear Mr. Vishnu,

With reference to your enquiry, we are pleased to submit our offer for the supply and installation of high temperature wall mounted axial fans for the oil refinery production area at the following locations:

- Ground Floor – Oil Refinery Production Area
- Second Floor – Oil Refinery Production Area

SCOPE OF WORK

1. Supply and installation of wall mounted axial fans with gravity shutters, and louvers with sand trap and bird screen. The fans will be operated through an ON/OFF switch only.
2. Fans are galvanized steel casing with RAL 9003 powder coating, die-cast aluminium aerofoil impellers with adjustable pitch, from the high temperature series rated for 300°C / 2 hrs.
3. Testing and commissioning of the installed fans upon availability of permanent power by others.

PRICE SCHEDULE

Item	Description	Qty	Unit	Unit Price (QAR)	Total (QAR)
1	**High Temperature Wall Mounted Axial Fan — Model AE 800-7/30** Airflow 24,975 m³/h @ 360 Pa static pressure; 5.5 kW, 4-pole, 1440 rpm, 415V/3Ph/50Hz, IP55, Class H motor; rated 300°C / 2 hrs.	1	No.	19,800.00	19,800.00
2	**High Temperature Wall Mounted Axial Fan — Model AE 450-5/30** Airflow 4,320 m³/h @ 160 Pa static pressure; 0.55 kW, 4-pole, 1440 rpm, 415V/3Ph/50Hz, IP55, Class H motor; rated 300°C / 2 hrs.	1	No.	10,440.00	10,440.00
3	**High Temperature Wall Mounted Axial Fan — Model AE 500-5/25** Airflow 5,587 m³/h @ 160 Pa static pressure; 0.55 kW, 4-pole, 1440 rpm, 415V/3Ph/50Hz, IP55, Class H motor; rated 300°C / 2 hrs.	1	No.	11,160.00	11,160.00
4	**High Temperature Wall Mounted Axial Fan — Model AE 800-7/30** Airflow 27,000 m³/h @ 340 Pa static pressure; 5.5 kW, 4-pole, 1440 rpm, 415V/3Ph/50Hz, IP55, Class H motor; rated 300°C / 2 hrs.	1	No.	19,800.00	19,800.00
5	**High Temperature Wall Mounted Axial Fan — Model AE 630-10/30** Airflow 13,200 m³/h @ 325 Pa static pressure; 2.2 kW, 4-pole, 1440 rpm, 415V/3Ph/50Hz, IP55, Class H motor; rated 300°C / 2 hrs.	1	No.	14,760.00	14,760.00

Item	Description	Qty	Unit	Unit Price (QAR)	Total (QAR)
6	**High Temperature Wall Mounted Axial Fan — Model AE 1000-7/30** Airflow 48,600 m³/h @ 400 Pa static pressure; 7.5 kW, 4-pole, 1440 rpm, 415V/3Ph/50Hz, IP55, Class H motor; rated 300°C / 2 hrs.	1	No.	24,480.00	24,480.00
				TOTAL LUMP SUM PRICE (QAR)	**100,440.00**
Amount in words: *Qatari Riyals One Hundred Thousand Four Hundred Forty Only.*					

EXCLUSIONS

- Civil works, including wall openings, making good and finishing.
- Electrical power cables, isolators and final terminations.
- Control panels — if required, will be quoted separately.
- Duct works — if required, will be quoted separately.
- Any item or service not explicitly mentioned in this quotation.

COMMERCIAL TERMS

Payment Terms	70% advance with LPO; 30% against completion.
Delivery	4 weeks from receipt of LPO and advance payment, subject to site readiness.
Warranty	12 months from date of completion against manufacturing defects.
Validity	30 days from the date of this quotation.
Prices	In Qatari Riyals (QAR), lump sum for the quantities listed. Any change in quantity or model will be adjusted accordingly.

We trust our offer meets your requirements and remain at your disposal for any clarification.

Yours faithfully,

METRI ENGINEERING SERVICES W.L.L.

