M/s SHIFT Qatar Attention: Ms. Edlyn Villaverde, Senior Procurement Officer Email: evillaverde@shift.qa **Tel:** +974 4450 3823 | **Mobile:** +974 5501 8163	**QREF 20/10/26-5** **SUBJECT: Cigar Lounge Smoke Issue – HVAC Assessment and Technical Solution** **Location: 44th Floor, Tornado Tower, West Bay, Doha**
DATE: 23-10-2023	**E-Mail: mes@mes.qa**

Dear Edlyn,

With reference to our site visit, we are pleased to submit our quotation for the assessment of the HVAC systems serving the cigar lounge, where smoke odour is currently noticeable in the adjacent areas. Please find our scope of work and commercial terms below.

1. Existing system

The cigar lounge (approx. 6.5 m × 7.0 m × 4.0 m high approx) is currently served by:

- One chilled water fan coil unit (FCU), approx. 14 kW cooling capacity
- One extraction fan, approx. 200 L/s, connected to an exhaust duct
- A fresh air duct connected to the FCU return
- Return diffusers fitted with charcoal (activated carbon) filters

2. Scope of work

2.1 Assessment of the existing HVAC systems

- Inspection of the FCU, exhaust fan, fresh air connection and carbon filters, including condition, and duct routing
- Measurement of existing airflows (supply, return, fresh air and exhaust) using calibrated TAB instruments, to establish a baseline
- Measurement of the room pressure relative to the adjacent areas

2.2 Technical solution and commercial proposal

- Assessment report with the measured baseline, findings and deficiencies
- Proposed technical solution to overcome the smoke issue, covering exhaust and fresh air rates, room pressurisation, air distribution and filtration
- Commercial proposal for the implementation of the proposed solution (quoted separately)

3. Commercial offer

Item	Description	Amount (QAR)
1	Assessment of existing HVAC systems serving the cigar lounge, airflow measurements, findings report and technical solution proposal, as per Section 2	5,000.00
	Total (lump sum)	**5,000.00**

Amount in words: Qatari Riyals Five Thousand Only.

4. Exclusions

- Any ceiling works, including opening and closing of false ceilings
- Implementation and rectification works arising from the assessment (to be quoted separately under item 2.2)

5. Terms and conditions

- **Payment terms:** 100% in advance, to mobilize our team with TAB instruments
- **Validity:** 10 days from the date of this quotation
- **Access:** site access to the cigar lounge and associated plant to be arranged by the client

We trust our offer meets your requirements. Should you need any clarification, please do not hesitate to contact us.

Best regards,

Metri Engineering Services W.L.L

